

APPENDIX D: IMPACTED USERS AND VESSELS DATA



IMPACTED USERS

Marine Contractors

- Advanced American Construction *DB 4100*
- Diversified Marine *DB Freedom*
- General Construction Company *DB General*
- JT Marine *DB Taylor*
- Manson Construction Company *Derrick No. 24*
- SDS Lumber Company *future shipment*

Federal Government

- USACE dredge *Yaquina*

Marine Industries and Fabricators

- Greenberry
- Thompson Metal Fab
- Vigor

Marine Contractors

Company: Advanced American Construction

Vessel: *DB 4100*

Company did not respond to request for information. Details provided below were included in the CRC NIR.

Marine Contractors

Owner: Advanced American Construction

Vessel: DB 4100

4100 DB

Equip. #3-10

Manitowoc 4100 Series 2 Vicon 225 Ton 1992
 Manufacturer Model Max Capacity Year



Item	Description	Unit	Quantity	Type
	Crane			
1	Line 1 (Main)	LBS	1000'	1 1/8" wire
	Line 2 (Whip)	LBS	450'	1 1/8" wire
	Line 3 (Whip)	LBS	450'	1 1/8" wire
	Boom Wire		760'	7/8" wire
2	Boom	Feet	180'	
3	Width / Outriggers	Feet	--	--
	Length / Outriggers	Feet	--	--
4	Height w/boom down	Feet	35' 14' 2"	--
5	Shipping Weight	LBS	450,572	--
	Trucks / Ship	EA	7	--
	Barge			
1	Width	Feet	60'	--
2	Length	Feet	105'	--
3	Depth	Feet	7'	--
4	Draft	Feet		
5	Rakes		1	--
6	Spuds	Feet	78 90	--
*	Serial Number: 413419			

Notes: Equipment on barge: 4100 (#3-10), Bulldog Gen Set 5 kw mounted on crane (no equip. no.), 25 kw multi-equip. Gen Set (#9-35), Hydra-Pac 4000, hydraulic unit for spuds (#10-01), 2 winches (#14-12 and #14-24). Deutz F3L1011F engine, replaced in 7/03.

Vessel Height Verification Sheet

By: Jennifer Rabby

Date: 23 July 2012

1. Company Name and/or Owner of Vessel and Contact Information

a. Name of company: Advanced American Construction

b. Name of contact: Mike Johns

c. Phone number (Office): [REDACTED] (Cell): [REDACTED]

d. Email: [REDACTED]

e. Address: 8444 NW St Helens Road City: Portland

State: OR Zip code: 97231

2. Vessel

a. ID: Serial No. 413419

b. Name: 4100 DB

c. Type: Crane Barge

d. USCG Document Number: _____

3. Vessel Configuration

a. Identify vessel configuration: Crane Barge

• Is a vessel specification sheet available? Yes

• Configuration shown on the sheet: No

• What is the lowest height configuration for transport? 35 feet

b. What is the gantry configuration? _____ Estimated gantry height: 35 Feet

c. Does the barge have spuds? Yes

• Height above waterline for travel? 92 Feet

• Can the spuds be removed for travel? Only for long distances upstream for big jobs;
not for work in the Portland Harbor

• Work and cost involved in removing spuds? ½-1 day

4. Vessel Location

a. Where is the vessel currently located? Kalama

b. Is it working on a job? Yes Is it tied up to shore? no

c. What is the best time to make a trip to the vessel? _____

5. Surveyed Measurements (measurements from spec sheet)

Gantry Height:	35
Water Level:	
Top of Boom:	
Height of Boom Hinge Pin:	
Boom Cradle:	
Top of Spud:	92

6. Vessel Height

Self-Reported		Heights from Spec sheet	
Air Draft:	90 feet (top of spuds)	Air Draft:	92
Air Gap:	10 feet	Air Gap:	10 feet
Water Level:	16 feet	Water Level:	16 feet
Total Height:	116 feet	Total Height:	118 feet

7. History Notes

Date	Item
2/20/2012	Contacted by Megan Nelson
3/8/2012	Returned River User Data Sheet for the Linde Marie via email
7/23/2012	Interviewed by Karl Krcma and Jennifer Rabby; Vessel specification sheets provided

Marine Contractors

Company: Diversified Marine

Vessel: *DB Freedom*

Company provided data sheets to the IBR Program. Data sheets are included below, followed by the information included in the CRC NIR.

EXISTING VESSEL DATA SHEET

Please fill out the data sheet below. Note if the vessel is no longer in service or used on the waterway. If the vessel is still in service on the waterway, review and update vessel information and provide data where the field is blank. If you have new vessels that travel under the Interstate Bridge (main channel) and/or the North Portland Harbor Bridge (Oregon Slough), please use the following link to complete a waterway user survey:



<https://www.interstatebridge.org/rivernavigation>. In addition, through the survey link, please note any future vessel or cargo plans you know of that might require different vessels to transit under the bridge.

Company/Owner Name: Diversified Marine, Inc.

Vessel Name:

DB Freedom

Vessel Type:

Derrick barge

Specialized Vessel (*e.g. limited maneuverability due to design or mode of operation. If yes, please describe*): Choose an item.

Vessel Category: Commercial

USCG Document Number:

507476

Primary Mooring Location (*waterway milepoint, if known*):

Type and quantity of cargo, if applicable:

Length (overall; ft):

152.1

Beam (width; ft):

60

Draft (ft) - depth of hull below waterline, fully laden:

11

Air Draft (ft) - height of highest fixed point above waterline, unladen:

119

Air Gap (ft) - desired clearance from highest fixed point to lowest part of bridge:

10

Safety Margin (ft) horizontal clearance required by vessel to navigate through the bridge:

Transit speed under Interstate Bridge and Load Configuration:

5 knts

Time of Year of Passage:

10

Tug Assistance Required: Choose an item.

YES

Frequency of passage under Interstate Bridge main channel (typical per month):

Jan _____ Feb _____ Mar _____ Apr _____ May _____ June _____

Jul _____ Aug _____ Sep _____ Oct _____ Nov _____ Dec _____

Frequency of passage under the North Portland Harbor Bridge (Oregon Slough):

Jan _____ Feb _____ Mar _____ Apr _____ May _____ June _____

Jul _____ Aug _____ Sep _____ Oct _____ Nov _____ Dec _____


Marine Contractors

Owner: Diversified Marine

Vessel: DB Freedom

CRANE BARGE "DB FREEDOM"

Official No. 507476



Dimensions:

- Length: 152
- Beam: 60'
- Depth: 12"
- Draft: 4'
- Boom: 160' to main fall
- Boom: 172' to main whip line

Capacities:

- Fuel: 10,000 gallons
- Lift 123.5 tons off stern
- Lift: 87.4 tons @ 50' radius
- Lift: 81.2 tons @ 60' radius
- Lift: 67 tons @ 80' radius
- Lift: 25 tons @ 160' radius

Regulatory:

- American Hoist & Derrick Co
American 305 Revolver
- Gross tonnage: 911 GRT

Machinery:

- Power: Diesel/Electric
- Generator: 375KW 480V
- Engine: C18

Auxiliaries:

- 3 drum 20,000#deck winch
- Twp (2) Aux hoist: 2 drum Skagit

Capabilities:


- Heavy Lifting
- Crane Service
- Salvage
- Pile Driving

DIVERSIFIED MARINE, INC.

PO Box 83723
(1801 N Marine Drive - 97217)
Portland OR 97283 USA

Phone: 503-289-2669
Fax: 503-289-2825
E-mail: kurt@dmipdx.com
Website: www.dmipdx.com

See more photos and videos of our equipment on our website.



FREEDOM
NAME

DIVERSIFIED MARINE
LOCATION

7-02-2012
DATE

Vessel Height Verification Sheet

By: Pete Geiger

Date: 2 July 2012

1. Company Name and/or Owner of Vessel and Contact Information

a. Name of company: Diversified Marine

b. Name of contact: Kurt Redd

c. Phone number (Office): [REDACTED] (Cell):

d. Email: [REDACTED]

e. Address: 1801 N Marine Drive City: Portland

State: OR Zip code: 97217

2. Vessel

a. ID: b. Name: DB Freedom

c. Type: Crane Barge d. USCG Document Number:

3. Vessel Configuration

a. Identify vessel configuration: Crane Barge

• Is a vessel specification sheet available? Yes

• Configuration shown on the sheet: Crane Up

• What is the lowest height configuration for transport? Crane down at ~ 34 Degrees
above horizontal, spuds up and pinned

b. What is the gantry configuration? Estimated gantry height: Not given

c. Does the barge have spuds? Yes at least two forward. Spuds currently down

• Height above waterline for travel? 85 Feet

• Can the spuds be removed for travel? Only in very special circumstances when they
travel far upriver on the Columbia

• Work and cost involved in removing spuds? 4 hours each spud to re-install; need to tie up to
a dock near the work area.

4. Vessel Location

- a. Where is the vessel currently located? Columbia River North Portland Harbor
- b. Is it working on a job? Yes while tied up Is it tied up to shore? yes
- c. What is the best time to make a trip to the vessel? Anytime just give him 1 day notice

5. Surveyed Measurements (all measurements NAVD 88)

Gantry Height:	77.3 feet
Water Level:	16.0 feet
Top of Boom:	Measured while working = 201.4 feet (71 degrees off horizontal) Estimated at travel angle (34 degrees off horizontal) = 135 feet
Height of Boom Hinge Pin:	39.1 feet
Boom Cradle:	42.9 feet
Top of Spud:	Not surveyed – spuds in down position

6. Vessel Height

Self-Reported		Surveyed (Top of Boom Estimated)	
Air Draft:	85 feet (Top of Spuds)	Air Draft:	119 Feet (Top of Crane)
Air Gap:	10 feet	Air Gap:	10 feet
Water Level:	16 feet CRD	Water Level:	16 feet CRD
Total Height:	111 feet	Total Height:	145 feet

7. History Notes

Date	Item
2/17/2012	Contacted by Megan Nelson
2/29/2012	Data sheet submitted
6/28/2012	Contacted by Pete Geiger for field measurement
7/2/2012	Field measured

Marine Contractors

Company: General Construction Company

Vessel: *DB General*

Company confirmed the information provided during the CRC NIR is still accurate (email confirmation included below). Vessel details that follow were included in the CRC NIR.

From: [Brian Carrico](#)
To: [Nicole McDermott](#)
Subject: Fw: Interstate Bridge Program
Date: Thursday, September 23, 2021 11:36:04 AM
Attachments: [image002.png](#)
[image003.png](#)
[image004.png](#)
[image005.png](#)

From: Kent.Boden <[REDACTED]>
Sent: Thursday, September 23, 2021 11:23 AM
To: Brian Carrico <[REDACTED]>
Cc: Todd.Wille <[REDACTED]>
Subject: Interstate Bridge Program

Hello Brian, there are three vessels no longer in service; the Beaver, Tacoma, and Anchorage. The remainder of the information is accurate. Please feel free to call me if you have any questions.



Kent Boden
Pursuits Manager, Kiewit Bridge & Marine

Kiewit Infrastructure West Co.
2200 Columbia House Blvd, Vancouver, WA 98661
[REDACTED] (P) [REDACTED] (C)
Kiewit.com An Equal Opportunity Employer

From: Brian Carrico <[REDACTED]>
Sent: Thursday, September 23, 2021 9:17 AM
To: Kent.Boden <[REDACTED]>
Subject: [EXTERNAL] Interstate Bridge Program

Kent - Thanks for taking my call today. Attached is the information submitted for the CRC program back in 2012. We would appreciate a review of this information to confirm that it remains accurate. We would especially want to know if any of the specifications have changed, if any of the fleet are no longer in service, if other vessels should be considered and whether you have any planned or potential projects that would result in the need to transit through the I-5 bridge area.

Feel free to contact me with any questions.

Brian

Brian Carrico
Interstate Bridge Replacement Program
Environmental Program

O: [REDACTED] | C: [REDACTED]

E: [REDACTED]

interstatebridge.org



Marine Contractors

Owner: General Construction

Vessel: D.B. General



**GENERAL
CONSTRUCTION
COMPANY**

D.B. GENERAL
700 TON FLOATING CRANE



SPECIFICATIONS

- Main Crane: Clyde 52
- Capacities: 700 tons @ 70' radius over the stern
500 tons @ 70' radius fully revolving
40 tons @ 243' radius (auxiliary)
25 tons @ 257' radius (whip)
- Boom: 200' to main fall (260' available)
230' to auxiliary line (290' available)
245' to whip line (305' available)
- Barge Size: 300' x 100' x 18'
- Classification: ABS+A1, USCG
- Draft (std.): 8'-0"
- Spuds: Two 48"Ø x 90' long
- Anchors: 6-point moorage
- Deck Loading: 2,000 psf uniform
- Bunkers: 50,000 gallons diesel fuel
310,000 gallons fresh water



CAPABILITIES

- Heavy Lifting
- Piledriving
- Offshore Construction & Service
- Duty Cycle – Dredging
- Pipe Lay

Columbia River CROSSING



River User Data Sheet

By: RALPH PETEREIT Date: 2/27/2012

1. Company Name and/or Owner of Vessel and contact information

Name of company: GENERAL CONSTRUCTION CO.

Name of contact: PAT BOYD - EQUIPMENT MANAGER

Phone number (Office): [REDACTED] (Cell): [REDACTED]

Email: [REDACTED]

Address: 3838 W. MARGINAL WAY SW

City: SEATTLE State: WA Zip code: 98106

3a. Vessel Name: D.B. GENERAL 3b. Vessel Type: FLOATING CRANE/
DERRICK BARGE

3c. US Coast Guard Document Number: _____

4a. Length Overall (LOA), feet: 300 4b. Beam (width), feet: 105.8

5. Draft (depth of hull below waterline, fully laden), feet: 8

6. Air Draft (Height of the highest fixed point of the vessel above the waterline, unladen), feet: 93

7. Air gap for vessel (desired clearance from the highest fixed point on the vessel to lowest part of bridge): 5-10

8. Frequency of one-way passage underneath I-5 main channel (typical per month):
Jan ___ Feb ___ Mar ___ Apr ___ May ___ Jun ___ Jul ___ Aug ___ Sep ___ Oct ___ Nov ___ Dec ___

9. Frequency of one-way passage underneath I-5 main channel (other historic events): _____

10. Frequency of one-way passage through North Portland Harbor (Oregon Slough) (typical per month): NONE
Jan ___ Feb ___ Mar ___ Apr ___ May ___ Jun ___ Jul ___ Aug ___ Sep ___ Oct ___ Nov ___ Dec ___

11. Frequency of one-way passage through North Portland Harbor (Oregon Slough) (other historic events): _____

12. Do you have a Business Plan (e.g. 10 or 20 year plan)? NOT AVAILABLE

What does it say regarding vessels transiting under the I-5 Bridge or into North Portland Harbor (Oregon Slough)? NOTHING IN THE WORKS FOR ANYTHING LARGER THAN THIS BARGE.

May we have a copy? _____

13. Other miscellaneous THIS IS GENERAL'S / KIEWIT'S LARGEST CRANE BARGE. IT HAS GONE UNDER THE BRIDGE TO TAKE THE CRANE OFF THE DAVY CROCKET MANY YEARS AGO, AS WELL AS SOME PICKS UP AT THOMSEN METAL FAB. - BUT CAN'T REMEMBER WHEN

River User Data Sheet

By: _____ Date: _____

1. Company Name and/or Owner of Vessel and contact information

- a. Name of company: GENERAL CONSTRUCTION COMPANY
- b. Name of contact: _____
- c. Phone number (Office): _____ d. (Cell): _____
- e. Email: _____
- f. Address: 33455 6th AVE S.
- g. City: FEDERAL WAY
- h. State: WA i. Zip code: 98003

3a. Vessel Name: D.B. GENERAL 3b. Vessel Type: CRANE BARGE

3c. US Coast Guard Document Number: 1042279

4a. Length Overall (LOA), feet: 288.0 4b. Beam (width), feet: 100.0

5. Draft (depth of hull below waterline, fully laden), feet: 8'

6. Air Draft (Height of the highest fixed point of the vessel above the waterline, unladen), feet: 93'

7. Air gap for vessel (desired clearance from the highest fixed point on the vessel to lowest part of bridge): 10'

8. Frequency of one-way passage underneath I-5 main channel (typical per month): _____
Jan ___ Feb ___ Mar ___ Apr ___ May ___ Jun ___ Jul ___ Aug ___ Sep ___ Oct ___ Nov ___ Dec ___

9. Frequency of one-way passage underneath I-5 main channel (other historic events): _____

10. Frequency of one-way passage through North Portland Harbor (Oregon Slough) (typical per month):
Jan ___ Feb ___ Mar ___ Apr ___ May ___ Jun ___ Jul ___ Aug ___ Sep ___ Oct ___ Nov ___ Dec ___

11. Frequency of one-way passage through North Portland Harbor (Oregon Slough) (other historic events): _____

12. Do you have a Business Plan (e.g. 10 or 20 year plan)? What does it say regarding vessels transiting under the I-5 Bridge or into North Portland Harbor (Oregon Slough)? May we have a copy?

13. Other miscellaneous

Vessel Height Verification Sheet

By: Ralph Petereit Date: July 10, 2012

1. Company Name and/or Owner of Vessel and Contact Information

- a. Name of company: General Construction Co.
- b. Name of contact: Pat Boyd – Equipment Manager
- c. Phone number (Office): [REDACTED] (Cell): [REDACTED]
- d. Email: [REDACTED]
- e. Address: 3838 W. Marginal Way City: Seattle
State: WA Zip code: 98106

2. Vessel

- a. ID: _____ b. Name: DB General
- c. Type: Crane Barge d. USCG Document Number: 1042279

3. Vessel Configuration

- a. Identify vessel configuration: Crane barge
- Is a vessel specification sheet available? Yes
 - Configuration shown on the sheet: Yes
 - What is the lowest height configuration for transport? 93 ft
- b. What is the gantry configuration? Pinned Estimated gantry height: 93 ft
- c. Does the barge have spuds? Yes
- Height above waterline for travel? Gantry height
 - Can the spuds be removed for travel? Yes
 - Work and cost involved in removing spuds? ½ - full day

4. Vessel Location

- a. Where is the vessel currently located? Terminal 105 – Doing day jobs in the Puget Sound Region
- b. Is it working on a job? Yes Is it tied up to shore? Depends on the day
- c. What is the best time to make a trip to the vessel? Need to call for daily schedule

5. Measurements from Spec Sheet


Gantry Height:	93 ft
Water Level:	
Top of Boom:	
Height of Boom Hinge Pin:	
Boom Cradle:	
Top of Spud:	

6. Vessel Height

Self-Reported		From Spec Sheet	
Air Draft:	93 ft	Air Draft:	93 ft
Air Gap:	5 – 10 ft	Air Gap:	10 ft
Water Level:	16	Water Level:	16
Total Height:	119 ft	Total Height:	119 ft

7. History Notes

Date	Item
6/29/2012	Contacted Pat Boyd- Equipment Manager
7/10/2012	Visited Yard to confirm vessel locations and heights




OUTBOARD PROFILE

ISSUED: JAN 2010
 FC-53-0736-2

D.B. GENERAL (700 TON) - #53-0736

GENERAL CONSTRUCTION COMPANY
 19472 POWDER HILL PL * POULSBRO, WA * 98370-7466
 (360) 779-3200 * FAX (360) 779-3132





DECK PLAN

ISSUED: JAN 2010
 FC-53-0736-3

D.B. GENERAL (700 TON) - #53-0736

GENERAL CONSTRUCTION COMPANY
 19472 POWDER HILL PL * POULSBORO, WA * 98370-7466
 (360) 779-3200 * FAX (360) 779-3132



Marine Contractors

Company: JT Marine

Vessel: *DB Taylor*

Company provided data sheets to the IBR Program. Data sheets are included below, followed by the information included in the CRC NIR.

EXISTING VESSEL DATA SHEET

Please fill out the data sheet below. Note if the vessel is no longer in service or used on the waterway. If the vessel is still in service on the waterway, review and update vessel information and provide data where the field is blank. If you have new vessels that travel under the Interstate Bridge (main channel) and/or the North Portland Harbor Bridge (Oregon Slough), please use the following link to complete a waterway user survey:



<https://www.interstatebridge.org/rivernavigation>. In addition, through the survey link, please note any future vessel or cargo plans you know of that might require different vessels to transit under the bridge.

Company/Owner Name: JT Marine, Inc.

Vessel Name:

DB Taylor

Vessel Type:

Crane barge

Specialized Vessel (e.g. limited maneuverability due to design or mode of operation. If yes, please describe): Choose an item.

Vessel Category: Commercial

USCG Document Number:

514786

Primary Mooring Location (waterway milepoint, if known):

Type and quantity of cargo, if applicable:

Length (overall; ft):

148

Beam (width; ft):

50

Draft (ft) - depth of hull below waterline, fully laden:

5

Air Draft (ft) - height of highest fixed point above waterline, unladen:

90' w/ spuds 75' w/ spuds out

Air Gap (ft) - desired clearance from highest fixed point to lowest part of bridge:

10

Safety Margin (ft) horizontal clearance required by vessel to navigate through the bridge:

60'

Transit speed under Interstate Bridge and Load Configuration:

Time of Year of Passage:

Tug Assistance Required: Choose an item.

Frequency of passage under Interstate Bridge main channel (typical per month):

Jan ___ 10 ___ Feb ___ 10 ___ Mar ___ 10 ___ Apr ___ 10 ___ May ___ 10 ___ June ___ 10 ___

Jul ___ 10 ___ Aug ___ 10 ___ Sep ___ 10 ___ Oct ___ 10 ___ Nov ___ 10 ___ Dec ___ 10 ___

Frequency of passage under the North Portland Harbor Bridge (Oregon Slough):

Jan ___ 1 ___ Feb ___ 1 ___ Mar ___ 1 ___ Apr ___ 1 ___ May ___ 1 ___ June ___ 1 ___

Jul ___ 1 ___ Aug ___ 1 ___ Sep ___ 1 ___ Oct ___ 1 ___ Nov ___ 1 ___ Dec ___ 1 ___

Marine Contractors

Owner: JT Marine

Vessel: DB Taylor



Columbia River CROSSING



River User Data Sheet

By: Irene T

Date: 3-22-2012

1. Company name and/or owner of vessel and contact information

Name of company: JT Marine Inc

Name of contact: Irene Torstora

Phone number (Office): [REDACTED]

(Cell):

Email: [REDACTED]

Address: 2301 SE Hidden Way, Suite 100

City: Vancouver

State: WA

Zip code: 98661

3a. Vessel name: DB Taylor

3b. Vessel type: Crane barge

3c. U.S. Coast Guard Document Number: 514786

4a. Length Overall (LOA), feet: 148'

4b. Beam (width), feet: 50'

5. Draft (depth of hull below waterline, fully laden), feet: 5'

6. Air Draft (Height of the highest fixed point of the vessel above the waterline, unladen), feet: ~~150~~ 143' as per

7. Air gap for vessel (desired clearance from the highest fixed point on the vessel to lowest part of bridge): 10'

8. Frequency of one-way passage underneath I-5 main channel (typical per month):

Jan 10 Feb 10 Mar 10 Apr 10 May 10 Jun 10 Jul 10 Aug 10 Sep 10 Oct 10 Nov 10 Dec 10

9. Frequency of one-way passage underneath I-5 main channel (other historic events):

10. Frequency of one-way passage through North Portland Harbor (Oregon Slough) (typical per month):

Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec


11. Frequency of one-way passage through North Portland Harbor (Oregon Slough) (other historic events):

12. Do you have a business plan (e.g. 10 or 20 year plan)? NO

What does it say related to vessels traveling under the I-5 Bridge or into North Portland Harbor (Oregon Slough)?

May we have a copy?

13. Other (additional sheets may be attached.) NA



DB TAYLOR

NAME

J.T. MARINE
MEASURED AT
SELLWOOD BRIDGE, PORTLAND, OR

LOCATION

07-12-12

DATE

Vessel Height Verification Sheet

By: Pete Geiger

Date: 12 July 2012

1. Company Name and/or Owner of Vessel and Contact Information

- a. Name of company: JT Marine
- b. Name of contact: Waino Toristoja
- c. Phone number (Office): [REDACTED] (Cell): [REDACTED]
- d. Email: [REDACTED]
- e. Address: 2301 SW Hidden Way, #100 City: Vancouver
State: WA Zip code: 98661

2. Vessel

- a. ID: _____ b. Name: DB Taylor
- c. Type: Crane Barge d. USCG Document Number: 514786

3. Vessel Configuration

- a. Identify vessel configuration: Crane Barge
 - Is a vessel specification sheet available? No
 - Configuration shown on the sheet: N/A
 - What is the lowest height configuration for transport? Crane down in cradle, spuds up and pinned
- b. What is the gantry configuration? Pinned Estimated gantry height: Not given
- c. Does the barge have spuds? Yes two midpoint. Spuds currently down
 - Height above waterline for travel? 80 Feet
 - Can the spuds be removed for travel? Only in very special circumstances when they travel far upriver on the Columbia
 - Work and cost involved in removing spuds? 4 hours each spud to re-install; need to tie up to a dock near the work area. Can lift both spuds with own crane.

4. Vessel Location

- a. Where is the vessel currently located? Willamette River Sellwood Bridge
- b. Is it working on a job? Yes Is it tied up to shore? No
- c. What is the best time to make a trip to the vessel? Anytime just give him 1 day notice

5. Surveyed Measurements (all measurements NAVD 88)

Gantry Height:	65.3 feet
Water Level:	13.8 feet
Top of Boom ¹ :	Measured while working = 192.7 feet (71 degrees off horizontal) Estimated height at travel angle: <ul style="list-style-type: none"> • 220 foot long boom: 131 feet • 166.6 foot long boom: 51 feet (limit is the gantry height)
Height of Boom Hinge Pin:	35.0 feet
Boom Cradle:	38.9 feet
Top of Spud:	62.4 feet – spuds in down position ²

¹ Note: JT Marine reported that they use two different booms on the DB Taylor; one with a length of 220 feet and one with a length of 166.6 feet.

² JT Marine self reported that the height to the top of their spuds are 80 feet.


6. Vessel Height


Self-Reported		Surveyed ¹	
166.6 foot boom		220 foot boom	
Air Draft:	80 feet (top of spuds)	Air Draft:	131 feet
Air Gap:	10 feet	Air Gap:	10 feet
Water Level:	16 feet CRD	Water Level:	16 feet CRD
Total Height:	106 feet	Total Height:	157 feet

¹ Note: The surveyed air draft measurement shown is the estimated travel height based on the surveyed boom length.

7. History Notes


Date	Item
3/27/2012	Contacted by Ron Del Rosario
3/28/2012	Data sheet submitted
6/28/2012	Contacted by Pete Geiger for field measurement
7/12/2012	Field measured






DERRICK BARGE TAYLOR MAIN HOOK — ALLOWABLE LOAD WITH 220 FOOT BOOM

McKERNAN FILE: P10-07
BY: JCMcK 2-12-11



Hi-Tech Metal Fabrication Inc. 2301 SE Hidden Way, Suite 100 Vancouver, WA 98661	CUSTOMER	SCALE	NA
	ADDRESS	DRAWN BY	WG
	ADDRESS	DATE	2/27/2011
		DRAWING #	
		REV	0
?		JOB #	



Marine Contractors

Company: Manson Construction Company

Vessel: *Derrick No. 24*

Company did not respond to request for information. Details provided below were included in the CRC NIR.

Marine Contractors

Owner: Manson Construction

Vessel: Derrick No. 24



Serving the Nation's Waterways Since 1905

Fleet

Derrick Barges/Clamshell Dredges "Derrick #24"



"Derrick #24" Specifications

Dimensions

Length:
200 ft / 60.9 m

Beam:
84 ft / 25.6 m

Depth:
13 ft / 3.96 m

Draft:
6 ft / 1.8 m

Operating Parameters

Maximum Linepull w/ boom
extended 65 ft (19.8 m):
800,000 lb / 3,558 kN

Fuel:
40,000 gal / 151,400

Columbia River CROSSING



River User Data Sheet

By: RALPH PETEREIT Date: 2/27/2012

1. Company Name and/or Owner of Vessel and contact information

Name of company: MANSON CONSTRUCTION CO.

Name of contact: RANDY THORSEN

Phone number (Office): [REDACTED] (Cell): [REDACTED]

Email: [REDACTED]

Address: 5209 E. MARGINAL WAY S.

City: SEATTLE State: WA Zip code: 98134

3a. Vessel Name: DERRICK NO. 24 3b. Vessel Type: FLOATING CRANE / DERRICK BARGE

3c. US Coast Guard Document Number: _____

4a. Length Overall (LOA), feet: 200 4b. Beam (width), feet: 90

5. Draft (depth of hull below waterline, fully laden), feet: 6

6. Air Draft (Height of the highest fixed point of the vessel above the waterline, unladen), feet: 99

7. Air gap for vessel (desired clearance from the highest fixed point on the vessel to lowest part of bridge): 5-10

8. Frequency of one-way passage underneath I-5 main channel (typical per month):

Jan ___ Feb ___ Mar ___ Apr ___ May ___ Jun ___ Jul ___ Aug ___ Sep ___ Oct ___ Nov ___ Dec ___

9. Frequency of one-way passage underneath I-5 main channel (other historic events): _____

10. Frequency of one-way passage through North Portland Harbor (Oregon Slough) (typical per month):

Jan ___ Feb ___ Mar ___ Apr ___ May ___ Jun ___ Jul ___ Aug ___ Sep ___ Oct ___ Nov ___ Dec ___

11. Frequency of one-way passage through North Portland Harbor (Oregon Slough) (other historic events): _____

12. Do you have a Business Plan (e.g. 10 or 20 year plan)? NOT AVAILABLE

What does it say regarding vessels transiting under the I-5 Bridge or into North Portland Harbor (Oregon Slough)? _____

May we have a copy? _____

13. Other miscellaneous LOCATED IN SEATTLE AND IS THE LARGEST

BARGE IN THE PACIFIC NW, THIS BARGE HAS NOT BEEN UP

THE COLUMBIA RIVER IN OVER 10 YEARS, NO CURRENT PLANS

TO RELOCATE THIS BARGE TO THE COLUMBIA RIVER.

Vessel Height Verification Sheet

By: Ralph Petereit Date: July 21, 2012

1. Company Name and/or Owner of Vessel and Contact Information

- a. Name of company: Manson Construction Co.
- b. Name of contact: Randy Thorsen – Northwest Operations Manager
- c. Phone number (Office): [REDACTED] (Cell): [REDACTED]
- d. Email: [REDACTED]
- e. Address: 5209 E. Marginal Way City: Seattle
State: WA Zip code: 98124

2. Vessel

- a. ID: _____ b. Name: Derrick 24
- c. Type: Crane Barge d. USCG Document Number: 657491

3. Vessel Configuration

- a. Identify vessel configuration: Crane Barge
- Is a vessel specification sheet available? Yes
 - Configuration shown on the sheet: Yes
 - What is the lowest height configuration for transport? Gantry Height
- b. What is the gantry configuration? _____ Estimated gantry height: 98 ft 7 in
- c. Does the barge have spuds? Yes
- Height above waterline for travel? 98 ft 7 in
 - Can the spuds be removed for travel? Yes
 - Work and cost involved in removing spuds? _____

4. Vessel Location

- a. Where is the vessel currently located? Lake Washington, WA.
- b. Is it working on a job? Yes – 520 Bridge Replacement Is it tied up to shore? No
- c. What is the best time to make a trip to the vessel? None currently

5. Measurements from Spec Sheet

Gantry Height:	98 ft 7 in
Water Level:	
Top of Boom:	
Height of Boom Hinge Pin:	
Boom Cradle:	
Top of Spud:	

6. Vessel Height

Self-Reported		From Spec Sheet	
Air Draft:	99 ft	Air Draft:	98 ft 7 in
Air Gap:	5 – 10 ft	Air Gap:	10
Water Level:	16	Water Level:	16
Total Height:	125 ft	Total Height:	124 ft 7 in



7. History Notes

Date	Item
6/27/2012	Called and left message for Randy Thorsen – NW Ops Manager
7/9/2012	Called Randy, was told to send e-mail
7/9/2012	Sent-mail with information request
7/21/2012	Still no reply

Principal Characteristics	
Length Overall	200'-0"
Beam Overall (With pontoons & Tires)	90'-0"
Beam Overall (With pontoons)	86'-2"
Beam Overall (W/O Pontoon)	78'-0"
Barge Depth	13'-0"
Minimum Draft	7'-0"
Distance Deck to Boom Heel	22'-3"
Boom Length to Main Block	185'-0"
Boom Length to 2-Part Whip	156'-0"
Boom Length to Whip	207'-2"
Boom Length Main to Whip	22'-0"
Spuds - 92' Each, Good to 70' Depth	2 - Each




Manson Derrick 24



Miscellaneous Characteristics	
Crane Manufacturer	Clyde Iron Works
Model Number	42-DE-145
Serial Number	CW 3931
Circle Diameter	42' Diameter
Rigging Wire	5,150' 1 1/4" 6x26
Main Hoist	1,150' 1 1/4" 6x26
2-Part Whip	550' 1" 6x26
Whip Line	5,250' 1 1/4" 6x26
Boom (Topping Gear)	
Spud Wire	
Side Spud	360' 1 1/4"
Stern Spud	360' 1 1/4"
Anchor Wire	
Stern Anchors (2)	1,700' 1 1/4" 6x26
Bow Anchors (2)	1,700' 1 1/4" 6x26
Normal Fuses Capacity	40,000 Gallons (1" = 307 Gallons)
Boom (Topping Gear)	3,000 Gallons

PRINCIPAL CHARACTERISTICS

LENGTH OVERALL	201'-0"
BEAM OVERALL (WITH PONTOONS & TIRES)	90'-0"
BEAM OVERALL (WITH PONTOONS)	86'-1 1/2"
BEAM OVERALL (W/O PONTOON)	78'-0"
BARGE DEPTH	13'-0"
DRAFT	22'-3 1/2"
DISTANCE DECK TO BOOM HEEL	FWD 6'-0" AFT 7'-0"
BOOM LENGTH TO MAIN BLOCK	185'-0"
BOOM LENGTH TO 2-PART WHIP	156'-6"
BOOM LENGTH TO WHIP	202'-0"
BOOM LENGTH MAIN TO WHIP	22'-0"
SPUDS - 92' EA., GOOD TO 70' DEPTH	2 EA.




MANSON DERRICK NO. #24

LIFT CAPACITY CHART IN POUNDS

BOOM RADIUS FEET	HEAVY LIFT	FULL REVOLVING	2 PART WHIP LINE	FULL REVOLVING
65'	800,000	185 FOOT BOOM	185 FOOT BOOM	185 FOOT BOOM
70'	800,000			
75'	800,000			
80'	739,000			
85'	671,700			
95'	563,300			
105'	479,500			
115'	412,100			
125'	356,500			
135'	309,200			
145'	268,100			
155'	231,600			
165'	198,400			
175'	167,300			
185'	137,100			
195'	105,500			

MISCELLANEOUS CHARACTERISTICS

CRANE MANUFACTURE	CLYDE IRON
MODEL NUMBER	42-DE-145
SERIAL NUMBER	CW 3931
CIRCLE DIAMETER	42' DIAMETER
RIGGING WIRE	5,350' 1 1/4" 6 X 26
MAIN HOIST	700' 1 1/4" 6 X 26
2-PART WHIP	600' 1 1/8" 18 X 19 DY18
WHIP LINE	5,240' 1 1/4" 6 X 26
BOOM (TOPPING GEAR)	
SPUD WIRE	360' 1 1/4" 6 X 26
SIDE SPUD	360' 1 1/4" 6 X 26
STERN SPUD	
ANCHOR WIRE	1,700' 1 1/4" 6 X 26
STERN ANCHOR'S (2)	1,700' 1 1/4" 6 X 26
BOW ANCHOR'S (2)	40,000 GALS.
NORMAL FUEL CAPACITY	3,000 GALS.
NORMAL WATER CAPACITY	



Marine Contractors

Company: SDS Lumber Company

Vessel: *Future Shipment*

Company did not respond to request for information. Details provided below were included in the CRC NIR for a potential future shipment including a barge and equipment loaded.

Commercial Tugs and Tows

Owner: SDS Lumber

Vessel: SDS Lumber Barge with Equipment



River User Data Sheet

By: Gary Collins Date: 3-13-12

1. Company Name and/or Owner of Vessel and contact information

- a. Name of company: SDS Lumber Co.
- b. Name of contact: Gary Collins
- c. Phone number (Office) [REDACTED] d. (Cell): [REDACTED]
- e. Email: [REDACTED]
- f. Address: PO Box 266
- g. City: Bingen WA
- h. State: WA i. Zip code: 98605

3a. Vessel Name: Darby 3b. Vessel Type: Tug

3c. US Coast Guard Document Number: _____

4a. Length Overall (LOA), feet: 86 4b. Beam (width), feet: 28

5. Draft (depth of hull below waterline, fully laden), feet: 8'

6. Air Draft (Height of the highest fixed point of the vessel above the waterline, unladen), feet: 55'

7. Air gap for vessel (desired clearance from the highest fixed point on the vessel to lowest part of bridge): 10'

8. Frequency of one-way passage underneath I-5 main channel (typical per month): 10
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec

9. Frequency of one-way passage underneath I-5 main channel (other historic events): _____

10. Frequency of one-way passage through North Portland Harbor (Oregon Slough) (typical per month):
Jan ___ Feb ___ Mar ___ Apr ___ May ___ Jun ___ Jul ___ Aug ___ Sep ___ Oct ___ Nov ___ Dec ___

11. Frequency of one-way passage through North Portland Harbor (Oregon Slough) (other historic events): 6

12. Do you have a Business Plan (e.g. 10 or 20 year plan)? What does it say regarding vessels transiting under the I-5 Bridge or into North Portland Harbor (Oregon Slough)? May we have a copy?

13. Other miscellaneous

Barges that might be higher
than Tug that has equipment
loaded on them could be as high
as 100' ?
1



Telephone Conversation Memorandum

project: Columbia River Cross job no. AH. 08.15 date: 15 Aug 2012
(use complete number)

from: Peter M. Geiger talked to: Gary Collins
SDSLumber

indicate department, field office, etc., "for in-house" calls.
indicate agency or firm for other than "in-house" calls.



item discussed: Status of Large Package Barges
Ability/Permission to Survey Air Draft

LW 8/15/12 1538 PDT 8/16/2012 0915 PDT via cell phone
information obtained:

9 Barges No Spuds on their Barges

Metal Fab Spud Barge Pushes

Most of their work is pushing other peoples
barges including Metal Fab (eg Thompson) or Construction
barges/Crane barges with Spuds. These services
are on an as-needed basis with nothing scheduled
in the near term.

action required:

distribution:

[Redacted distribution list]

by:

Federal Government

Agency: USACE

Vessel: *Yaquina*

USACE confirmed the information provided during the CRC NIR is still accurate (email confirmation included below). Vessel details that follow were included in the CRC NIR.

From: [Hicks, Jeffrey T CIV USARMY CENWP \(USA\)](#)
To: [Brian Carrico](#)
Cc: [Nicole McDermott](#); [Darlene Siegel](#)
Subject: RE: Interstate Bridge Replacement Project - USACE vessels/Navigation needs
Date: Tuesday, June 8, 2021 8:43:19 AM
Attachments: [image001.png](#)
[image002.png](#)
[image003.png](#)
[image004.png](#)

Brian,

I did just get a response on the upcoming planned activities from our Operating Project Managers.

The Yaquina looks to be the tallest USACE vessel that we expect to transit through the area. Annual O&M dredging's in water work window is 1 August to 30 September but we need to have the ability to address shoals at any time of year. I believe that's how we landed on the river level + Yaq height clearance in our formal letter to the CRC.

As far as future work goes, our contractors often move equipment and materials via barge to construction projects. For example recent gate replacements, JD AWS electrical building, etc along with the large cranes mobilized to handle these. The largest crane I've heard coming up river was "The General" which I think Kiewit now owns.

I am trying to verify the dimensions of "the General" as well as the largest items we've moved under contract (likely The Dalles or John Day Gates). Otherwise there is nothing planned that would be impacted by the bridge height.

Thanks, Jeff

Jeff Hicks | Portland District Project Manager

☎: [REDACTED] | [REDACTED]

From: Brian Carrico <[REDACTED]>
Sent: Tuesday, June 8, 2021 8:14 AM
To: Hicks, Jeffrey T CIV USARMY CENWP (USA) <[REDACTED]>
Cc: Nicole McDermott <[REDACTED]>; Darlene Siegel <[REDACTED]>
Subject: [Non-DoD Source] Re: Interstate Bridge Replacement Project - USACE vessels/Navigation needs

Jeff, it has been a few weeks since sending this. I wanted to check in with you to see if you need further information from the team in order to complete this request and/or if you have

an estimate for when we may get the information. Thanks in advance.

Brian

From: Brian Carrico <[REDACTED]>
Sent: Thursday, May 13, 2021 10:22 AM
To: Hicks, Jeffrey T CIV USARMY CENWP (USA) <[REDACTED]>
Cc: Nicole McDermott <[REDACTED]>; Darlene Siegel <[REDACTED]>
Subject: Re: Interstate Bridge Replacement Project - USACE vessels/Navigation needs

Jeff - attached is the information provided for CRC.

Brian

From: Hicks, Jeffrey T CIV USARMY CENWP (USA) <[REDACTED]>
Sent: Thursday, May 13, 2021 10:16 AM
To: Brian Carrico <[REDACTED]>
Cc: Nicole McDermott <[REDACTED]>; Darlene Siegel <[REDACTED]>
Subject: RE: Interstate Bridge Replacement Project - USACE vessels/Navigation needs

Hey Brian,

Sorry for the slow response. I would be the correct contact to validate this information. I am working with our Navigation team to answer this question but as far as I'm tracking it was just the Yaquina. Hoping I can get you a formal response by tomorrow.

Thanks, Jeff

From: Brian Carrico <[REDACTED]>
Sent: Wednesday, May 12, 2021 8:01 AM
To: Hicks, Jeffrey T CIV USARMY CENWP (USA) <[REDACTED]>
Cc: Nicole McDermott <[REDACTED]>; Darlene Siegel <[REDACTED]>
Subject: [Non-DoD Source] Interstate Bridge Replacement Project - USACE vessels/Navigation needs

Jeff,

I am part of the team working on the Interstate Bridge (IBR) Program addressing the USCG permit. We are collecting information on vessel use of the Columbia River and are validating and updating the data provided by the USACE for the prior Columbia River Crossing Project.

The information at that time was provided by Marci Johnson. Would you be the best contact for validating the information? Specifically, I am looking to confirm information on the Yaquina, whether any other USACE vessels would be expected to transit through the area (either North Portland Harbor or the main channel) and whether there are any planned activities at upstream dams would require specific shipments under the bridge in the future.

Thanks in advance. Feel free to call or email if you have questions or need additional information.

Brian

Brian Carrico

**Interstate Bridge Replacement Program
Environmental Program**

O: [REDACTED] | **C:** [REDACTED]

E: [REDACTED]

interstatebridge.org



Federal Government

Owner: US Army Corps of Engineers

Vessel: Yaquina



Columbia River CROSSING



River User Data Sheet

By: NWP Dredge OPS

Date: Feb 27, 2012

1. Company Name and/or Owner of Vessel and contact information

Name of company: US Army Corps of Engineers, Portland District

Name of contact: Marci Johnson

Phone number (Office): ([REDACTED]) (Cell): _____

Email: [REDACTED]

Address: 333 SW 1st Avenue, P.O. Box 2946

City: Portland State: OR Zip code: 97204

3a. Vessel Name: Yaquina 3b. Vessel Type: Hopper Dredge

3c. US Coast Guard Document Number: CG000073

4a. Length Overall (LOA), feet: 200 4b. Beam (width), feet: 58

5. Draft (depth of hull below waterline, fully laden), feet: 16

6. Air Draft (Height of the highest fixed point of the vessel above the waterline, unladen), feet: 92

7. Air gap for vessel (desired clearance from the highest fixed point on the vessel to lowest part of bridge): 8

8. Frequency of one-way passage underneath I-5 main channel (typical per month): based on historical
Jan 2 Feb 2 Mar 2 Apr 2 May 2 Jun 2 Jul 2 Aug 4 Sep 4 Oct 2 Nov 2 Dec 2

9. Frequency of one-way passage underneath I-5 main channel (other historic events): included in 8.

10. Frequency of one-way passage through North Portland Harbor (Oregon Slough) (typical per month):
Jan 0 Feb 0 Mar 0 Apr 0 May 0 Jun 0 Jul 0 Aug 0 Sep 0 Oct 0 Nov 0 Dec 0

11. Frequency of one-way passage through North Portland Harbor (Oregon Slough) (other historic events): none

12. Do you have a Business Plan (e.g. 10 or 20 year plan)? provided by letter dated Feb 23, 2012

What does it say regarding vessels transiting under the I-5 Bridge or into North Portland Harbor (Oregon Slough)? _____

May we have a copy? _____

13. Other miscellaneous Historical information provided above does not represent future needs. Future needs were provided to CRC by letter dated Feb, 23 2012. As stated in Feb 23, 2012 letter, to ensure safe passage of the dredge Yaquina, the minimum bridge height required for current and future operational needs is 116 feet CRD.



Vessel Height Verification Sheet

By: Karl Krcma Date: July 26, 2012

1. Company Name and/or Owner of Vessel and Contact Information

- a. Name of company: US Army Corps of Engineers
- b. Name of contact: Marci Johnson
- c. Phone number (Office): [REDACTED] (Cell):
- d. Email: [REDACTED]
- e. Address: 333 SW 1st Ave, PO Box 2946 City: Portland
- State: OR Zip code: 97204

2. Vessel

- a. ID: b. Name: Yaquina
- c. Type: Hopper Dredge d. USCG Document Number: CG000073

3. Vessel Configuration

- a. Identify vessel configuration: Self propelled hopper dredge
- Is a vessel specification sheet available? No
 - Configuration shown on the sheet: N/A
 - What is the lowest height configuration for transport? 92 feet
- b. What is the gantry configuration? N/A Estimated gantry height: N/A
- c. Does the barge have spuds? N/A
- Height above waterline for travel? N/A
 - Can the spuds be removed for travel? N/A
 - Work and cost involved in removing spuds? N/A

4. Vessel Location

- a. Where is the vessel currently located? N/A
- b. Is it working on a job? N/A Is it tied up to shore? N/A
- c. What is the best time to make a trip to the vessel? N/A

5. Measurements from Spec Sheet

Gantry Height:	N/A
Water Level:	N/A
Top of Boom:	N/A
Height of Boom Hinge Pin:	N/A
Boom Cradle:	N/A
Top of Spud:	N/A

6. Vessel Height

Self-Reported		Surveyed	
Air Draft:	92	Air Draft:	90 (draft at bow 12-12.5 and draft stern 11-11.5)
Air Gap:	10	Air Gap:	10
Water Level:	16	Water Level:	16
Total Height:	118 feet	Total Height:	116 feet

7. History Notes

Date	Item
2/14/2012	Contacted by Karl Krcma
2/27/2012	River user data sheet submitted
7/17/2012	Surveyed





DEPARTMENT OF THE ARMY
CORPS OF ENGINEERS, PORTLAND DISTRICT
PO BOX 2946
PORTLAND OR 97208-2946

REPLY TO
ATTENTION OF

FEB 23 2012

Planning, Programs and Project
Management Division

Ms. Heather Wills
Columbia River Crossing
700 Washington Street, Suite 300
Vancouver, Washington 98660

Dear Ms. Wills,


This letter is in response to the Columbia River Crossing (CRC), Interstate 5 (I-5) Project boat survey request for information regarding the Corps Dredges Yaquina and Essayons and our navigational needs upstream of the proposed new I-5 bridge project.

We determined that the proposed bridge height outlined in the Record of Decision would have serious impacts on our federal missions to maintain the navigation channel and provide emergency dredging upstream of the new bridge. After considering dredging requirements and potential future water release impacts to the Columbia River, we determined that the minimum prism needed for the new bridge is a height of 116 feet Columbia River Datum (121.4 NAVD88) for a width of 400 feet. A more detailed explanation of our requirements is enclosed.

We will forward a copy of this letter to Rear Admiral Keith Taylor, Commander 13th District United States Coast Guard, Jackson Federal Building, 915 Second Avenue, Seattle, WA 98174-1067, John McAvoy, FHWA, 610 East 10th Street, Vancouver, WA 98661; and Dave Hendricks, Multnomah County Drainage District No. 1, 1880 NE Elrod Dr., Portland, Oregon 97211.

We look forward to resolving these navigation concerns to ensure the CRC project does not have any unacceptable impacts to our federal projects. Please feel free to contact me at [REDACTED] or Ms. Marci Johnson of my staff at [REDACTED] or via e-mail at [REDACTED]

Sincerely,


John W. Eisenhauer, P.E.
Colonel, Army Corps of Engineers
District Commander

Enclosure



**US Army Corps
of Engineers**®
Portland District

**U. S. Army Corps of Engineers Federal Navigation Channel Maintenance Needs
Columbia River Crossing (I-5 Interstate Bridge at Vancouver, WA)
February 2012**

Summary:

Minimum prism needed for new bridge is height 116 feet Columbia River Datum (CRD) (equal to 121.4 feet NAVD88) for width 400 feet (channel width of 300 feet plus 50 feet on each side of the channel).

Authorized project:


- The federal Navigation Channel immediately upstream of the Columbia River Crossing is authorized to 27 feet deep and 300 feet wide from Vancouver, WA, to The Dalles, OR. This channel supports the Columbia-Snake river system and transportation of 10 million tons of cargo annually. It is the largest wheat/barley export gateway in the U.S. and the third largest grain export gateway in the world.

Minimum bridge prism reasoning:

- The Corps' Dredge *Yaquina* performs annual channel maintenance dredging. The minimum prism needed for the new bridge is the vertical clearance required for this dredge to pass safely under the bridge at a specified river water level above CRD, and the horizontal clearance required for maintenance of the channel under the bridge.

Vertical clearance discussion:

- According to the USCG-licensed captains of the Dredge *Yaquina*, a 100-foot minimum vertical clearance from top of water to bottom of bridge is required (draft of 9 feet below the waterline gives a height of 92 feet above the waterline, plus an 8-foot minimum safety gap).
- The environmentally protective in-water work period as established by Federal and State agencies has changed in the past, and could continue to change as new species are listed, requiring work to be done during periods of higher river flow and stage.
- Year-round river flow levels must be considered as emergency operations could be required at any time. The probability of a river stage is shown below, using available data from the past 20 years.



- The uncertainty of future water levels must be considered. As part of the Columbia River Treaty Review, the Corps is collecting new data and performing studies to evaluate maintaining or potentially changing current levels of regulation for flood risk protection in this region of the Columbia River basin. The National Marine Fisheries Biological Opinion for the Federal Columbia River Power System also requires the Corps to spill water at its Columbia River dams to support salmon survival. These factors may lead to future operations resulting in elevated river levels (closer to ordinary high water) for longer durations compared with the past 20 years. Current Regulatory ordinary high water level at the Columbia River Crossing is 16 feet CRD (equivalent to 21.4 feet NAVD88).
- Bridge lift records show the lift height in feet above zero at the bridge pier elevation (39 feet CRD). Recent records show that the median lift for the Dredge *Yaquina* is 100 feet (equal to 139 feet CRD). The maximum lift shown was 136 feet (175 feet CRD). The minimum lift shown was 90 feet (129 feet CRD). Water levels shown on bridge records corresponding to these lifts ranged from 1 to 12 feet CRD.

Vertical clearance conclusion: A minimum vertical height of 116 feet CRD (121.4 feet NAVD88) is required. Year-round river level data from the past 20 years indicate that river levels were at or below 16 feet CRD approximately 98 percent of the time. Future river operations will likely increase river levels up to ordinary high water (16 feet CRD) for longer periods. Adding the 100-foot vertical clearance from waterline to bridge required for the Dredge *Yaquina* to 16 feet CRD yields a minimum vertical bridge height requirement of 116 feet CRD (121.4 NAVD88).

Horizontal clearance discussion:

- The Corps practices advanced width maintenance dredging (dredging up to 50-100 feet outside the channel width) to provide an area outside the channel for unstable side slope sloughing so that the full channel width remains clean.

Horizontal clearance conclusion: A horizontal width of 400 feet CRD is required at the vertical height specified above. This width includes the channel width (300 feet) plus 50 feet additional width on each side of the channel for advanced width maintenance dredging.

Marine Industries and Fabricators

Company: Greenberry

Company provided the following information to the IBR Program.

EXISTING VESSEL DATA SHEET

Please fill out the data sheet below. Note if the vessel is no longer in service or used on the waterway. If the vessel is still in service on the waterway, review and update vessel information and provide data where the field is blank. If you have new vessels that travel under the Interstate Bridge (main channel) and/or the North Portland Harbor Bridge (Oregon Slough), please use the following link to complete a waterway user survey:



<https://www.interstatebridge.org/rivernavigation>. In addition, through the survey link, please note any future vessel or cargo plans you know of that might require different vessels to transit under the bridge.

Company/Owner Name: Greenberry Industrial LLC

Vessel Name:

Third-party

Vessel Type:

Barge and Tug

Specialized Vessel (*e.g. limited maneuverability due to design or mode of operation. If yes, please describe*):**Yes**

Tugboat towing barge

Vessel Category: Commercial

USCG Document Number:

Third-party

Primary Mooring Location (*waterway milepoint, if known*):

N/A

Type and quantity of cargo, if applicable:

Modules, Process modules, piperacks, MCC buildings, Alaska Sealift Modules, Drill Rigs, Pressure Vessels, Shiploaders, Piling Templates, Vessels, Bridge Girders, Bridge Components, Railroad Bridges, DOT Bridge Sections, Autoclaves, Slugcatcher Vessels, Port Assemblies, Material Handling Systems, Conveyor Systems, Dock Sections, Bridge Maintenance Travelers, and various other over-dimensional fabricated items.

Length (overall; ft):

650 Feet

Beam (width; ft):

120 Feet

Draft (ft) - depth of hull below waterline, fully laden:

18ft

Air Draft (ft) - height of highest fixed point above waterline, unladen:

136 Feet

Air Gap (ft) - desired clearance from highest fixed point to lowest part of bridge:

1 Foot

Safety Margin (ft) horizontal clearance required by vessel to navigate through the bridge:

10 Feet?

Transit speed under Interstate Bridge and Load Configuration:

10-12kts MAX

Time of Year of Passage:

Year round

Tug Assistance Required:Yes

Frequency of passage under Interstate Bridge main channel (typical per month):

Jan ___ 1 ___ Feb ___ 1 ___ Mar ___ 1 ___ Apr ___ 1 ___ May ___ 1 ___ June ___ 1 ___

Jul ___ 1 ___ Aug ___ 1 ___ Sep ___ 1 ___ Oct ___ 1 ___ Nov ___ 1 ___ Dec ___ 1 ___

Frequency of passage under the North Portland Harbor Bridge (Oregon Slough):

Jan ___ 0 ___ Feb ___ 0 ___ Mar ___ 0 ___ Apr ___ 0 ___ May ___ 0 ___ June ___ 0 ___

Jul ___ 0 ___ Aug ___ 0 ___ Sep ___ 0 ___ Oct ___ 0 ___ Nov ___ 0 ___ Dec ___ 0 ___

Marine Industries and Fabricators

Company: Thompson Metal Fab

Company provided the following information to the IBR Program.



THOMPSON
METAL FAB




















Interstate Bridge Replacement Project





Thompson Metal Fab – Impact Statement

May 26, 2021

Presented by John Rudi
Owner, President – Thompson Metal Fab

 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Table of Contents	PG 1 of 1

-  **INTRODUCTION 1**
-  **COLUMBIA BUSINESS CENTER 2**
-  **THOMPSON METAL FAB 4**
 -  *Marine/Hydro 5*
 -  *Tanks/Vessels 8*
 -  *Bridge 9*
 -  *Modular/Structural 11*
 -  *Oil & Gas 14*
-  **LOCAL BENEFIT & LOOKING AHEAD 24**
 -  *Willow Expansion/Pikka Expansion/Horseshoe Unit 26*
 -  *Aerospace 28*
 -  *Offshore Wind and Wave 30*
 -  *Burnside Bridge 32*
 -  *Golden Gate Bridge Seismic Retrofit 33*
 -  *West Coast Moveable Bridges 33*
 -  *Hydroelectric Maintenance Projects 33*
 -  *Desalination in California 35*
 -  *Wartime Efforts 35*
-  **IN CLOSING 35**

-  **ATTACHMENTS**
 -  **APPENDIX A – Bridge Clearance Visual Aid**
 -  **APPENDIX B – River Usage Data**
 -  **APPENDIX C – Photo Gallery**



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 1 of 36

INTRODUCTION

The history of Thompson Metal Fab includes two major influences, the opening of the Interstate Bridge in 1917, and the opening of the Columbia Business Center (*originally Henry Kaiser's Vancouver Shipyard*) in 1942. Over the years, Thompson Metal Fab (TMF), the Columbia Business Center (CBC) and the Interstate Bridge will see their history evolve due to the changing needs of the region, rapid population growth, and dynamic industrial development. For these same reasons, their history also begins to connect, and their futures are tied together.



The original Thompson Metal Fab facility, shown in 2018. Thompson moved from this location and to Vancouver in the early 1970's. The old facility has since been demolished, making way for the brand new Meyer Memorial Trust building.



Original span of the Interstate Bridge opened 1917 – shown here in 1931.

The original Interstate Bridge (current day northbound span) was completed and opened in February of 1917. Upon completion of this span, travelers could go from Canada to Mexico on one complete roadway. This was not only a big accomplishment for the country, but it was also an opportunity for growth, specifically in southwestern Washington. At the time the bridge was opened, there were approximately 250,000 people in Portland, compared to the 12,000 in Vancouver. The new bridge would provide opportunity for dynamic population movement, economic growth, and forever connect not only two states, but two communities. To satisfy the needs of this expanding community, a second 'twin' span was eventually completed and opened in 1958.

With a clearance of 72 feet, most river barges can pass under the bridge without impact when the drawbridge is closed. This is not the case with large industrial projects, like those manufactured currently by Thompson Metal Fab, or for large vessels, like the Liberty and Victory ships from the early 1940's. At full height, the current lift span can accommodate 178' from the water to the underside of the bridge. This "air gap" allows very large loads to pass upriver and downriver and has driven the development of upstream industrial areas such as the Columbia Business Center, originally known as Henry Kaiser's Vancouver Shipyard.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 2 of 36

COLUMBIA BUSINESS CENTER (former Kaiser Vancouver Shipyard)



Building 40 and 41 of current day Thompson Metal Fab is shown prominently in the middle of this picture. At the time this picture was taken (circa early 1940's) the building and entire industrial area would have been known as Kaiser's Vancouver Shipyards.

At nearly 200-acres, Kaiser's Vancouver Shipyard began production in early 1942 with an initial payroll of 38,000 workers. This facility, along with two in Portland, produced 752 ships during WWII and peaked at 97,000 workers in total. Many of these workers migrated from other parts of the country and is part of the reason why the Portland/Vancouver area saw such a big jump in population at this time. The development of these shipyards certainly contributed to the need for a new span (eventually built and completed in 1958) and the need to modify the original span, completed in 1960. For perspective on what these facilities were able to produce, the construction on the first Liberty ship took 131 days in 1941. By 1943, Kaiser workers were averaging a completed Liberty ship in 42-days and three ships were being completed each day. Record production for a completed ship was 10-days, although that production was bested by one of the Kaiser facilities in Richmond, CA (4-days, 15-hours, 29-minutes).



[1943] Escort carriers at the Vancouver Shipyards (current day Thompson Metal Fab)



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 3 of 36



75,000 people (largest crowd in Clark County's history) assembled on April 5, 1943 to witness first lady Eleanor Roosevelt christen the 'Alazon Bay' escort aircraft. Current day Thompson Metal Fab is seen prominently in the background.

After the war ended and the need for shipbuilding diminished, learning how to leverage these 'abandoned' facilities for future industrial growth was important. The size of the facility at the Vancouver Shipyard was simply greater than most fabrication shops of the day. Even now, it remains one of the largest fabrication facilities on the West Coast. The sheer size of the building, access to a large yard, and location to a major waterway made the facility at the future Columbia Business Center an extremely attractive option for the large infrastructure needs that were coming.

The Portland/Vancouver Metro area became highly industrialized by the 1960's, driven by the ability of the Columbia Business Center and companies such as Thompson Metal Fab. This strong local economy centered around logging, pulp & paper products, and maritime transport on the Columbia River; and stimulated additional growth in the region. The California oil boom would also

drive opportunity to the Columbia Business Center as oil companies looked for fabricators to build "jacket liners" for new offshore wells. The facility could support the work on the massive infrastructure and the bridge was high enough to allow the jacket liners to be shipped downstream.

The 1960's and 1970's saw the construction of new dams on the Columbia River and Snake River in addition to the development of major oil fields in Alaska (i.e. Prudhoe Bay). Ongoing work on the US Interstate Highway System also provided opportunity for new bridges, including four highly visible bridges in Portland: Morrison Bridge (1958), Marquam Bridge (1966), Freemont Bridge (1973), and the Glenn L. Jackson Memorial Bridge (1982). These would be opened to accommodate a shifting population and to relieve pressure on traffic crossing the Interstate Bridge.



Infrastructure for the California offshore oil fields being manufactured at the Columbia Business Center in 1967. Thompson Metal Fab would begin operations here a few years later in 1973.

 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 4 of 36

THOMPSON METAL FAB

In 1937, “Pudge” Thompson opens ‘Thompson Metal Fab’ at 2405 Vancouver Avenue in Portland, OR. The opening of his facility comes 20-years after the opening of the Interstate Bridge while also pre-dating the second span by 20-years.



The origin story of Thompson Metal Fab is a humble one, especially compared to the work they do today. Pudge and his craftsmen manufactured lightweight metal products for the dairy and timber industries. One product, the Thompson Ice Tongs, held US patent #D206,091 and a quick Google search shows that the Thompson Ice Tongs are still selling online to this day. Thanks in part to the WWII war effort, expansion of TMF continued during the 1940’s and 1950’s; mirroring the growth of the community it served and the new industrial opportunities.

Original marketing display of the Thompson Ice Tongs

In 1973, after 36 years, Pudge Thompson sold his company to Harder Mechanical, whose story is like TMF’s. Harder began as a small local plumbing contractor who was founded in 1934. A few years later they reinvented themselves so they could build housing for the workers at the Portland area shipyards during WWII. As the region continued to see growth, so did Harder who saw the acquisition of Thompson Metal Fab as a way to expand their capabilities and stake a claim on some of these emerging industries (i.e. hydroelectric dams). Shortly after the acquisition, the original Thompson Metal Fab facility (Portland, OR) was closed for good, and all operations were moved to the old Kaiser Shipyard in Vancouver, WA – a facility well suited to support the large projects Harder Mechanical would earn as they grew and expanded.

Thompson Metal Fab would transfer ownership again in the early 2000’s with even more emphasis on how to maximize the capacity. The size of the facility requires TMF to be a diversified business and one with experience in multiple disciplines, including:

Marine/Hydro



Tanks/Vessels



Bridges



Modular/Structural



Oil & Gas





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 5 of 36

Since the early 1970's, TMF has completed countless projects while working over 10-Million man-hours (*estimated*). The following list showcases some of the completed projects over the last 40+ years. In each case, transportation by barge was required (either by design or necessity), and in many cases the load passed under the Interstate Bridge.

Projects noted with () were not completed by Thompson Metal Fab but are on this list to showcase examples of other mega projects where a facility like Thompson's was required (Big shop, assembly yard, barge loading capabilities)*



MARINE/HYDRO

The Dalles Dam, Downstream Navigation Lock Miter Gates, Columbia River, WA/OR, USA [2011]

Two Miter Gates were manufactured, where each gate measured 52' W x 106' L and weighed 1-Million pounds each. Due to navigational lock closures on the Columbia River, an aggressive fabrication and delivery schedule was required which required a fabricator with ample space and ability to load a barge. Picture to the right shows one gate getting ready to be loaded on the barge. Seen in the background is Parker Drilling Rig 272 & 273. Those rigs would ship just a few months after this load.



Lower Monumental Dam, Downstream Navigation Lock Lift Gate, Snake River, WA, USA [2010]

The finished weight of this structure was 1.5-Million pounds and would ship to the jobsite by barge in three segments. The final gate is 88' W x 84' H

Ice Harbor Dam, Removable Spillway Weir, Snake River, WA, USA [2005]

This removable spillway weir is designed to move juvenile fish more efficiently through the dam spillways. The unit measured 70' in width x 68' in height x 105' in length. It weighed 950-tons and is taller than Thompson's facility! The weir was completely fabricated at TMF and then transported by barge to Cascade General for repositioning before shipping to the jobsite on the Snake River.





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 6 of 36

Lower Granite Dam, Removable Spillway Weir, Snake River, WA, USA [2001]

The removable spillway weir is designed to move juvenile fish more efficiently downstream through the dam spillways. The weir was 83' wide x 61' deep x 115' long and weighed approximately 1,000-tons. The weir was completely fabricated at TMF and then transported by barge to Cascade General for repositioning before shipping to the jobsite on the Snake River.



Esperanza 124 MW Power Barge [1999]

Recently retrofitted in 2017 in Panama, it was originally fabricated in 1999 by Thompson Metal Fab, and transported to Cascade General in Portland, OR for final assembly and functional testing. The barge measured 105' wide x 30' deep x 284' long with a weight of 1,800-tons. The completed barge was loaded on a 400' L x 100' W barge for delivery to Cascade General.



Golmar Explorer Ship Conversion [1997]

In 1997, Thompson fabricated multiple items for the infamous Golmar Explorer ship which was developed for the CIA and at the direction of Howard Hughes. By the mid-1990's the ship had changed hands a few times over and was in the process of being converted into an oil drilling vessel. TMF fabricated two double-bottom sections, four thruster tubs, vessel exhaust stacks, and manifold systems for this project. Completed components were transported by barge from TMF to Cascade General Shipyard.



 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 7 of 36

John Day Dam, Upstream Navigation Lock Gate, Columbia River, WA/OR, USA [1991]

This gate was fabricated at the Columbia Business Center. The gate measured 28' deep x 80' high x 120' wide and weighed 105-tons. It was transported standing (80' high) for installation purposes.


Pacific Marine Hull Fabrication, Honolulu, HI, USA [1989]

TMF fabricated a 365-ton "SWATH" (Small Waterplane Area Twin Hull) excursion vessel. The fabrication consisted of twin cigar-shaped hulls that were 9' in diameter and 132' in length with vessel beams measuring 53'. Thompson's location adjacent to the Columbia River proved valuable for launching the vessel. After sea trials, the "Navatek" vessel headed to Hawaii. The vessel is still operating today.



Christensen Shipbuilders, Dry Dock, Vancouver, WA, USA [1987]

210' long dry dock was fabricated by TMF, including all walls, deck, ballast tanks and piping



Columbia River Barge Conversions [1979-1971]

Thompson converted barges to carry wood chips in support of the pulp and paper mills. The converted barges were fabricated to ABS and USCG standards. Projects were installed at our adjacent dock and barge facilities.

Alaska Ferry Conversion [1973]

Thompson Metal Fab supplied an exhaust funnel, solarium structure and modular subcomponents for the passenger ferry that travels the Inland Passage to Alaska. The existing ferry was cut in half and lengthened, with TMF fabricating all components for this major renovation. All items delivered by barge to the shipyard.

Other Examples Include:

- WSDOT Coleman Dock Improvements [2023] *
- Ballard Lock & Dam, Navigation Lock Center Miter Gates, Lake Washington, WA, USA [2022] *

 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 8 of 36

- John Day Dam, 150-Ton Gantry Crane, Columbia River, OR/WA, USA [2022] *
- McNary Dam, Intake Bulkhead Gates, Columbia River, OR/WA, USA [2022] *
- Port of Alaska Petroleum & Cement Terminal Expansion, Anchorage, Alaska, USA [2021]
- Ward Cove Ferry Dock Expansion, Ward Cove, Alaska, USA [2020]
- WSDOT Mukilteo Dock Improvements, Mukilteo, WA, USA [2020] *
- The Dalles Dam, Upstream Navigation Lock Radial Gate, Columbia River, OR/WA, USA [2016] *
- Lower Granite Dam Expansion, Snake River, Washington, USA [1987]
- Revelstoke Dam, Columbia River, British Columbia, Canada [1984] *
- Bonneville Dam Expansion, Columbia River, Oregon, USA [1981] *
- Brownlee Dam Expansion, Snake River, ID/OR, USA [1980] *
- American Falls Dam Replacement, Snake River, ID, USA [1978] *
- Ice Harbor Dam Expansion, Snake River, Washington, USA [1976] *
- Grand Coulee Dam Expansion, Columbia River, Washington, USA [1974] *
- Mica Dam, Columbia River, British Columbia, Canada [1973] *
- John Day Dam, Columbia River, WA/OR, USA [1971] *
- Little Goose Dam, Snake River, Washington, USA [1970] *
- Lower Monumental Dam, Snake River, Washington, USA [1969] *



TANKS/VESSELS

Phillips 66 Prefractioner Tower, Rodeo, CA, USA [2015]

The 200-ton tower stretched 126' Long and transitions from 10'-6" diameter at the smallest to 17'-0" at the largest. The vessel was manufactured in three separate sections before being married together at Thompson's shop. The vessel shell and heads are made from clad plate which provides the necessary strength while also providing the required corrosion protection on the interior. For final acceptance, nearly 120,000 gallons of water was pumped into the vessel for a leak test. The vessel was pressurized over a period to ensure that all welds were water-tight.





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 9 of 36

REC Solar Grade Silicon Project, Moses Lake, WA, USA [2007]


Thompson Metal Fab manufactured a total of 10 process vessels for the solar grade silicon industry. The project included four vessels which required barge transportation due to their size. Those vessels were 150" ID x nearly 120'-0" L and weighed over 200,000 LBS/ea. Vessels were barged to Pasco, WA and then shipped over the road to Moses Lake.



BRIDGE

Sellwood Bridge, Portland, OR, USA [2016]

Thompson's scope of supply included fabrication of all major bridge components: Arches, Arch Cross-frames, Vertical Spandrels, and the Bridge Deck Steel. Over 5,000-tons in total. The distinctive feature of the bridge are the three arches which cover 1,275' of the total 1,976' crossing. Each arch was fabricated in segments, with each segment 100' long. Because of the project's location on the Willamette River, steel was delivered to the jobsite with seven barge loads. Multiple barges can be seen here with incoming steel deliveries.



 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 10 of 36

Bay Bridge Connector, Bay Area, CA, USA [2006]

TMF painted two orthotropic tub girders that were fabricated at the Columbia Business Center. Each weighed more than 1,600-tons and measured over 200' L x 80' W. Girders were transported by barge to the Bay Area for erection.

Richmond San Rafael Bridge, Bay Area, CA, USA [2004]

10,000 tons of structural bridge steel for the substructure was supplied for a seismic retrofit. Total fabrication took three years to complete. Larger components were transported by barge and direct to the jobsite.

Tri-Met Terry Moore Pedestrian Bridge, Portland, OR, USA [1996]

Fabricated at the Columbia Business Center, TMF painted the pedestrian bridge spanning HWY 26 near the HWY 217 junction. Completed sections were shipped by barge to a nearby location before being trucked to the jobsite.

1st Ave & Duwamish Bascule Bridge, Seattle, WA, USA [1996]

Completed truss sections for this project were fabricated at the Columbia Business Center, painted by Thompson, and assembled at the facility. Transportation to the jobsite in Seattle was done over the water, by barge.

Nimitz Freeway, Bay Area, CA, USA [1995]

This project consisted of (13) curved tub girders for the reconstruction of the Nimitz Freeway in the Bay Area. Girders were fabricated at the Columbia Business Center and painted by TMF. The total project weighed 6,000-tons with the largest girders weighing 450-tons; 50' W x 250' L. This project required four barges for delivery to jobsite..

I-90 East Channel Bridge, Seattle, WA, USA [1986]

Trapezoidal tub girders that varied from 98' to 198' in length and weighed between 60 and 200-tons each were fabricated at the Columbia Business Center and painted by Thompson Metal Fab. Girders were pre-assembled and completed sections loaded on a barge for transport to Lake Washington.



Other Examples Include:

- BNSF Bridge 66.4 Replacement, Cook, WA, USA [2020] *
- BNSF Bridge 58.8 Replacement, Home Valley, WA, USA [2019] *
- Wittpenn Bridge, Jersey City, NJ, USA [2017] *
- Sauvie Island Bridge, Portland, OR, USA [2004] *
- Glenn L. Jackson Bridge, WA/OR, USA [1982] *
- Freemont Bridge, Portland, OR, USA [1973] *

 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 11 of 36



MODULAR/STRUCTURAL

Intel Expansion, Hillsboro, OR, USA [2010's - Present]

Expansion at the Intel facility in Hillsboro has been going on for some time and Thompson has supplied numerous modular structures in support of their effort. In 2020, TMF shipped the largest modules to date, buildings that were 44' W x 97' L x 16' H. Due to their size, the buildings could break apart in half, but still required a barge to get from TMF's facility to the jobsite as shipping over the road was not an option.



Caltrans, East Tie-In Project, Bay Area, CA, USA [2008-2009]

Thompson was selected by Caltrans (owner) to work with TY-Lin (designer), CC Myers (contractor) and DCCI (erector) to fabricate 3,100-tons of temporary steel to provide detour for the Oakland Bay Bridge at Yerba Vista Island. Thanks to the size of their facility TMF could meet the 'expedited' schedule requirement for this project. Major components required four barge loads from TMF's facility to the job-site in California. Project was completed in 2009.

OHSU Tram, Portland, OR, USA [2006]

TMF fabricated the center support tower, the lower station, and the upper station for the tram project. The major components were transported by barge from TMF to the jobsite in Portland, OR where they were offloaded and erected.





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 12 of 36



The team at Thompson Metal Fab standing in front of base of the iconic Portland Aerial Tram mid-tower. The tram is located at the OHSU hospital in Portland and spans across I-405. The tower base is over 40' high as shown in this picture.

Alaska Gold Mining Project, Nome, Alaska, USA [2005]

Thompson fabricated hoppers, grizzly grates, ball mill chutes, structural supports, modification of the ball mill, and other mining equipment for this project. TMF's facility was used for the marshaling yard and the load out point for all equipment and structures. Delivery was made via barge to Nome, AK.

Boeing Delta IV Launch Table,
Vandenberg AFB, CA, USA [2003]

The 98' long x 33' high x 46' wide launch table weighed 580-tons. The project also included large flame deflector components which weighed up to 120-tons. The launch table and flame deflectors were fully assembled at the TMF facility and transported by barge to Vandenberg Air Force Base in California. It was then off-loaded and installed at the launch site.






Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 13 of 36

PGE Decommissioning Trojan Nuclear Reactor Project, Rainier, OR, USA [1998]

TMF fabricated a 120-ton transport structure and 5" THK shielding enclosures. The completed structures were shipped by barge to the jobsite where the decommissioned reactor was loaded. The entire load was then shipped by barge to the final storage location at Hanford – Richland, WA.



Powell River Paper Company, British Columbia, CANADA [1991]

Thompson supplied the fabricated steel for a Chlorine Dioxide Module that measured 35' wide x 76' high x 35' long. This module weighed 350-tons and was transported by barge in the vertical position from TMF's facility in Vancouver, WA to the Power River Paper Company in British Columbia, Canada.

Georgia Pacific Wood Chip Material Handling System, Toledo, OR, USA [1973]

TMF fabricated six 280' tube conveyor sections and all support towers for this project. The completed structures were transported by barge to Toledo, OR and installed.



 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 14 of 36


Other Examples Include:

- Data Centers, The Dalles, OR, USA [2010's – Present] *
- Data Centers, Hermiston, OR, USA [2010's – Present] *
- Pre-Heater Tower, Richmond, British Columbia, CANADA [1997]
- Portland Expo Center, Portland, OR, USA [1995]
- Bulk Material Handling System, Sacramento, CA, USA [1993]
- Newport Bay Floating Restaurant, Portland, OR, USA [1986]



OIL & GAS

The turnkey modular service TMF offers today reflects what kicked off in the 1980's. By that point work at Prudhoe Bay was ongoing, but the infrastructure needed to support the development was still in process. In 1984, Thompson supported ARCO by manufacturing two 96-room housing modules. Each module was 40' wide x 46' high x 80' long. In addition, two Utilidor Modules were manufactured (*each 10' W x 22' H x 24 L*). In 1985, more infrastructure was sent to ARCO; these 'bases' were 33' wide x 100' long x 10' high. Thompson also supported Conoco's Milne Point unit in 1985 with the supply of (10) module bases and (11) skids. These structures weighed anywhere from 20 to 270 tons each, with a max dimension of 64' W x 123' L x 12' H. Manufacturing structures of this size and delivering complete to the jobsite seems strange in the lower-48, but given the expanse of the North Slope, it's well suited to receive large infrastructure without other physical limitations to navigate. Additionally, with as fast as the development was happening, there was a value placed on 'set it and leave it' projects; things that could be installed and immediately put-to-use.





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 15 of 36



Massive platforms for the Alaska oilfields being fabricated at Thompson Metal Fab in the mid-1980's. The platforms nearly took up the entire width of a bay (80')



The platforms (seen left) were delivered by barge to Alaska where high capacity trucks and dollies (shown above) off loaded the structures for delivery to the jobsite.


Thompson's experience in supplying the oil fields eventually led to connections with the drilling contractors. The drilling contractors work on behalf of the owners to drill production wells and test holes as part of the exploration process. Drillers operate large equipment (known as rigs) to drill the holes. Thompson's first experience with rigs started in the late 1980's with Pool Arctic (*now Nabors Drilling*) who was a drilling contractor working on Alaska's North Slope. At one point, Pool Arctic operated the largest fleet of drill rigs on the North Slope. When TMF began working for Pool, they were looking to expand their fleet to meet market demand. This required retrofitting current rigs due to advances in equipment technology and drilling conditions that surpassed the capability of their rigs. Retrofitting works the same way as a new-build, only backwards. In a retrofit, the rig is placed on the barge and then shipped to a location large enough to receive it over the water and with enough yard space to accommodate the work. There are very few facilities on the West Coast who can accommodate this. Retrofits are just as attractive to TMF as new-builds. During a retrofit it is not unusual for some level of "rigging down" to happen and for structures to be placed in the shop. In that circumstance, it is very attractive to contractors to work with a facility large enough to handle these structures and keep them under the roof and out of the elements.



AADC merged with Pool Arctic in 1983 and provided the rig shown above as part of the merger. This rig would be retrofitted by TMF.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 16 of 36



Modular fabrication at Thompson Metal Fab for a Pool Arctic retrofit. The modules shown here represent the scale of a 'truckable' module, typically 12' H x 10' W x 40' L

Traditionally, drill rigs are built by manufacturing a series of truckable modules. These modules are fully assembled at the manufacturer's yard for verification, testing, and commissioning. Upon approval, the rig is completely disassembled for transportation to the jobsite. "Rigging up" is the process by which all these truckable modules are then reconnected together and recommissioned. Depending on the size of the rig, it is not unusual for 200 truckloads to be needed to move from the manufacturing location to jobsite. The process of putting a rig back together in remote locations can take months and cuts into production time. The ability to offer a turnkey service and integrate work in Thompson's shop and in their yard ultimately saves money in the long run – and contractors and owners have come to expect the capacity TMF can

offer. During the early development of Prudhoe Bay in the Arctic, machinery and field services were limited and getting the required equipment to the jobsite required creative solutions. Field work is expensive and risky; and often there is limitations to what can be performed. Thompson can build larger modules for delivery, which provides a distinct advantage by minimizing costs in the field and minimizing risk.

Parker Drilling was one of the first contractors who recognized that one solution to the problems on the North Slope was to simply to deliver a *bigger* rig. A bigger rig would be capable of holding more robust equipment which would allow for drilling longer, bigger holes for greater production. The benefit of drilling longer holes is that you do not need to move the rig from pad to pad as frequently; you can cover a lot more ground from just one spot. They understood the importance of downtime and the full capacity of what TMF could offer with regards to turnkey modular fabrication. The design for Parker Drilling's Rig 245 swapped out the multiple, smaller, truckable



A large module for Parker Drilling Rig 245 moving from TMF's shop to their yard for assembly. Seen in the background is the mast and substructure of this massive drilling rig.



Rig 245 shown here at the assembly yard. When fully raised, the mast hangs high in the Vancouver, WA skyline.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 17 of 36

modules and consolidated them into fewer ‘mega modules.’ Less modules simply take less time to put back together in the field. What could be 4-6 months in field work could now be up and running in weeks. Also, by eliminating trucks, the risk of loads being damaged during transport is reduced dramatically. Parkers’ vision of ‘mega modules’ required a facility that offered a few things: a big shop, big yard, skilled workforce, access to water for shipping, and a logistically friendly location.



Parker Drilling Rig 245 being ‘rigged up’ at Thompson Metal Fab’s yard. This yard space is immediately adjacent to the manufacturing facility and to the roll-on/roll-off barge slip. The ability to offer turnkey projects and delivery via water has given Thompson Metal Fab an advantage in the marketplace.

Drilling equipment has long been manufactured in Houston, Louisiana, and other Gulf state locations. These facilities manufacture the truckable modules and often the large offshore platforms. They certainly have the shop, yard, workforce, and access to water – but they do not have a strategic location to Alaska when it comes to logistics. To get a barge from the Gulf to the North Slope requires passage through the Panama Canal just to get from one side of the continent to the other. The added time for shipping and the added cost of voyage does not justify the mega module concept. What is needed is a manufacturer in the Pacific Northwest. TMF’s location at the old Kaiser shipyard in Vancouver, WA provides the space and direct access to a deep-water barge slip with roll-on/roll-off access. The combination of a heavy-industrial construction facility and a support yard with marine transportation capability is an important asset to the region’s industrial job base and has potential to attract large job producing projects. This capability has enabled TMF to stay competitive in a business that has largely moved overseas.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 18 of 36

Becoming a proven West Coast manufacturer of drilling equipment gave drilling contractors an option that was not there previously. By entering the market, engineers could now extend the limits of their design and present solutions that were attractive to both contractors and owners who were seeking to replicate what Parker did with Rig 245, the first mega-rig on the North Slope. Among the design variables that has always been taken into consideration are the shipping clearances between our facility and the North Slope of Alaska. In that distance, there are three bridges which loads must pass under: The Interstate Bridge, the Lewis & Clark Bridge, and the Astoria-Megler Bridge. Of those three, the Interstate has the lowest total clearance, but is currently sufficient to meet the requirements of transporting mega modules.



Doyon Drilling Rig 25 shown on the barge in the foreground. Due to the size of the rig and its six mega-modules, two barges were required for delivery to Alaska's North Slope. The background shows the remaining modules for Rig 25, in addition to Parker Drilling's AADU Rigs (Rig 272 and Rig 273)

Thompson's greatest competitive advantage in earning business with the drilling contractors is their ability to ship completed, commissioned, turn-key 'mega modules' to the jobsite. If that advantage is eliminated, they will be priced out of the market. In addition to competing against the Gulf states, they actively compete with Canadian shops in Alberta. Because of the exchange rate, those facilities have a 30% pricing advantage, all other things being equal. That is the magnitude of the shipping advantage they have at Thompson. Contractors are willing to pay a



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 19 of 36



Picture of the Interstate Bridge in 2011 showing both the original Northbound span (background) and the second span (foreground) which opened in 1958 to traffic in both directions. In 1960, the second span was dedicated to Southbound traffic only. (Photo shows TMF manufactured drill rigs, AADU Rig 272 & 273 for Parker Drilling)

premium to avoid truckable modules manufactured in interior Canada or in the Gulf. It is the Contractor's advantage in the long term to have mega modules as their risk is lower, their down time is lower, field erection and trucking costs diminish, etc. Please note, these mega modules can only have their loads diminished so much (because of shipping clearance issues, etc.) before the concept no longer makes sense and the design is forced back to a more traditional build plan.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 20 of 36

PROJECT EXAMPLES:

Hilcorp Innovation Rig, North Slope, Alaska, USA [2016]

The Innovation Rig is the next generation of drilling equipment. At nearly 1.5-Million LBS of steel, this rig consists of multiple modules and was built up to 50' H in TMF's shop before moving to their yard for final fit-up. At 9-months, this was the fastest rig build in Thompson's history, a true testament to their size and capability.



Parker Drilling AADU Rig 272 & 273, North Slope, Alaska, USA [2011]

Each drilling rig was comprised of three main modules. The Mud Modules weigh 600-tons, the Drill Modules weigh 700-tons, and the Utility Modules weigh 460-tons. The Mud and Utility Modules are 48' wide x 55' high x 99' long. The Drill Module is 76' high with the mast in the lay-down position.



Doyon Drilling Rig 25, North Slope, Alaska, USA [2010]

4-million LBS of steel and aluminum fabricated for Rig 25, a project where TMF also acted as the General Contractor. TMF managed all rig-up activities including mechanical, electrical, and functional checkout. This rig consisted of six primary modules: Power Complex (550-tons, 56' L x 40' W x 42' H); Drill Complex (560-tons, 96' L x 37' W x 40' H); Pipe Complex (560-tons, 68' L x 47' W x 25' H); Mud Complex (550-tons, 68' L x 40' W x 49' H); Pump Complex (560-tons, 64' L x 40' W x 52' H); Casing Complex (500-tons, 60' L x 56' W x 40' H). The 26' x 25' Mast extends to 148' L.





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 21 of 36

Parker Drilling/British Petroleum Liberty Rig, North Slope, Alaska, USA [2009]



This drilling rig shipped from our facility to the North Slope of Alaska in July 2009. TMF furnished approximately 5.5-million pounds of fabricated steel. The rig was the world's largest land-based rig at the time of manufacturing and consisted of three large modules. The Drill Module was 58' W x 98' H x 68' L, weighing 900-tons. The Pipe Barn module was 158' W x 45' H x 170' L, weighing 2,560-tons. The Drill Service Module was 50' W x 48' H x 177' L, weighing 2,600-tons.





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 22 of 36

Pool Arctic Rig 6, North Slope, Alaska, USA [1998]

The Rig 6 project was a retrofit of the existing rig and included all new structural framing in addition to new mechanical components for the moving system. At the time of manufacturing, it was reported by the tire manufacturer to be the largest rubber tire vehicle in the world. Nicknamed 'Radio Flyer', this backbone of this rig is twin 6' x 10' box girders which support the drill floor and mast, and transfers load to the substructure.



Nordic Calista Rig 3, North Slope, Alaska, USA [1998]

In 1998, TMF completed and delivered Modular Mobile Oil Drilling Rig 3 to Nordic Calista. The rig includes 850-tons of fabricated steel, it measures 45' wide x 78' high x 110' long. The rig was transported by barge to the North Slope of Alaska.



Parker Drilling Rig 245, North Slope, Alaska, USA [1990]

In 1990, TMF fabricated a self-propelled mobile oil drilling rig. The drilling module was 43' wide x 78' high x 150' long and weighed 3,000-tons. The utility module was 40' wide x 58' high and 130' long, weighing 1,500-tons. The cutting module is 30' wide x 30' high x 40' L, weighing 350-tons. The completed drilling rig was transported by ocean-going barge from TMF's facility to the North Slope.

ConocoPhillips Milne Point, North Slope, Alaska, USA [1987]

3,400-tons of fabricated modular steel structures were supplied to ConocoPhillips. This took three ocean-going barge loads to deliver to Alaska.

ARCO Operation Center Housing Expansion, North Slope, Alaska, USA [1985]

Modular superstructures (40' W x 65' H x 80' L) were fabricated along with bases and decking housing modules. Completed modules were loaded onto a barge and transported direct to the North Slope.





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 23 of 36

Other Examples Include:

- Crowley, Monopod Pile, Cook Inlet, Alaska, USA [2014]
- Saxon Rig 147 Retrofit, Cook Inlet, Alaska, USA [2013]
- Saxon Rig 169 Retrofit, Cook Inlet, Alaska, USA [2013]
- Kuukpik Rig 5 Retrofit, North Slope, Alaska, USA [2005]
- Pool Arctic Rig 9, North Slope, Alaska, USA [1999]
- Nordic-Calista Rig 1 Retrofit, North Slope, Alaska, USA [1997]
- Pool Arctic Rig 4, North Slope, Alaska, USA [1994]
- Petro Star Refinery (Valdez), Alaska, USA [1993] *
- Pool Arctic Rig 3, North Slope, Alaska, USA [1990]
- Petro Star Refinery (North Star), Alaska, USA [1985] *
- Trans Alaska Pipeline System (TAPS), Alaska, USA [1977]
- Prudhoe Bay, Alaska, USA
 - *Discovered (1968), Start of Production (1977), Peak Production (1988)*
- Cherry Point Refinery, Washington, USA [1971] *
- Cook Inlet Monopod, Cook Inlet, Alaska, USA [1970's] *
- Kenai Refinery, Alaska, USA [1969] *
- Maintenance on California refining facilities
- Maintenance on Washington refining facilities



With a structural height of 126', this pile template for a monopod in the Cook Inlet (Alaska) is one of the largest structures to ship from the Columbia Business Center in the last 40-years. Thompson Metal Fab manufactured piling for this project, delivered in 2014.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 24 of 36



Taken in the early 1970's, the photo above shows Thompson Metal Fab shortly after closing the original facility in Portland and moving to Vancouver. Thompson added fiberglass roofing and walls to bays 5 through 9 to create an enclosed space. The land has been developed quite a bit in the last 40-years (including improvements to the roll-on/roll-off barge slip), but the building remains virtually the same.

LOCAL BENEFIT & LOOKING AHEAD

Because of Thompson's 40-year reputation, logistical advantage and modern quality programs required, they have a distinct benefit. Loss of that logistical advantage due to a diminished shipping clearance (or other) is not something they could replace. Earning this business is a tremendous benefit to Thompson, their employees, and their local community. For example, any one rig project is equivalent to one year of revenues, in addition to hundreds of direct high wage jobs, as well as work for hundreds of local small businesses.

Due to the magnitude of work, contractors often mobilize to Vancouver to manage the construction. This includes management, engineers, and other personnel to ensure that projects are delivered on time. This staff of people stay long-term in local hotels, rent from local citizens, spend entertainment dollars with local small businesses, and are an economic benefit. They not only employ the staff at TMF, but they also employ local electricians, machinists, painters, millwrights, pipe fitters, hydraulic operators, boilermakers, sheet metal workers, and other trades. This work also supports various apprentice programs which train the next generation of trade workers. Loss of this total benefit cannot be replaced.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 25 of 36



Local businesses see boosts in revenues when major job producing projects are brought to the Columbia Business Center. Due to the nature of these large projects, stakeholders often move management teams to Vancouver to oversee manufacturing.

History has shown us that building a new link between Vancouver and Portland will bond our communities together and provide opportunity for economic growth and expansion. We also see that there is a correlation between the bridge, the growth of our community, and Thompson Metal Fab. The need for large-scale fabrication remains and markets that require TMF's services show no sign of slowing. There is potential for an industrial rebirth, one that mimics the industrial expansion of the 1950's through 1970's. While it is yet to be seen at the time of this writing, the federal government will at some point pass an infrastructure spending bill, which intends to replace our aging and deteriorating bridges, dams, and other critical works. Just as building these original structures kept generations of people working, so will the effort to replace these structures.

Thompson is encouraged by the commitment made to develop renewable energy sources. TMF has directly supported this effort for decades by manufacturing equipment that grows polysilicon crystals used in the development of solar panels. They have even been successful exporting domestically manufactured polysilicon equipment to countries such as China. Being a part of clean and renewable projects is something TMF does every day, thanks to the nature of their business. Steel is the most recycled material on Earth and steel products are 100% recyclable at the end of their useful life. Once produced, steel can be continually recycled into a new steel product without deterioration in product quality. Even the byproducts of steel work can be reused. Weld slag is used in cement, road construction, fertilizers, and hydraulic engineering. Process gasses are used to produce heat and electricity. Metal oxides can be recovered from steel making dust. Steel's inherent durability and recyclability make it an ideal fit for a circular economy. Allowing Thompson Metal Fab to continue producing steel products in the manner they do currently is a critical component in the continued development of clean energy and in effort to reduce America's carbon footprint.

As Thompson looks ahead to the future, they are currently tracking several projects and emerging markets which will certainly require a shop of their size and skill set. These projects will likely require delivery by barge and be of scale greater than or equal to what has been demonstrated. As noted, TMF has a competitive advantage with projects that require delivery by water and there is no other comparable, active facility with a roll-on/roll-off barge slip on the West Coast. Future opportunities include:


- ConocoPhillips – Willow expansion (*drill rigs, modules*)
- Oil Search – Pikka expansion (*drill rigs, modules*)



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 26 of 36

- Horseshoe Unit – Future North Slope Expansion (*drill rigs, modules*)
- Aerospace
- Offshore Wind and Wave power generators
- Burnside Bridge
- Golden Gate Bridge Seismic Retrofit
- West Coast Movable Bridges
- Hydroelectric Maintenance Projects
- Desalination in California
- Port of Nome - Expansion

Willow Expansion/Pikka Expansion/Horseshoe Unit





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 27 of 36

In many regards, the original Prudhoe Bay development has reached the end of its useful life. In 2020 original Owner, BP, sold their Prudhoe rights to ConocoPhillips and Hilcorp. Hilcorp is renowned for their ability to acquire ‘legacy wells’ and get a high level of production thanks to their ability to match modern technology with lean processes. What bigger companies might steer away from or flat out abandon due to high overheads, Hilcorp (a smaller independent company) can come in and still make profits for many years. The sale of Prudhoe and acquisition by Hilcorp signals the end of an era at Prudhoe, but it also marks the beginning of Alaska’s next chapter in oil production.

In 2016, discovery wells were drilled in the Willow unit, owned by ConocoPhillips. The Willow unit is immediately west of Prudhoe and other large operating units but is on land that is largely under-developed. During the expansion of Prudhoe Bay facilities were tied into one another (Alpine, Kuparuk, Oooguruk, Milne Point, North Star, Endicott), man camps often shared, and roads and bridges integrated into one logistical network. Willow is far enough outside of this integrated network that relying on the existing infrastructure to support further expansion is not feasible. New piping systems would be needed, new roads would be required, new processing modules installed, and essentially a ‘mini Prudhoe’ would need to be built from scratch. After a successful exploration and appraisal season in 2018 it is estimated that Willow could contain up to 750-million barrels of oil and the infrastructure that would support Willow could produce approximately 100,000 barrels per day. Assuming full production each day of the year, Willow would be ‘on-line’ for 20-years.



This massive process module is being loaded out for delivery to the North Slope of Alaska in July 1990. This industrial equipment rivals the size of most downtown buildings and is representative of the equipment currently being requested for North Slope expansion projects. Due to scale and complex nature of work, this sort of equipment cannot be manufactured at the remote jobsite or accomplished at all in Alaska.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 28 of 36



This massive process module is being loaded out for delivery to the North Slope of Alaska in July 1990. This industrial equipment rivals the size of most downtown buildings and is representative of the equipment currently being requested for North Slope expansion projects.

Flanked by existing units, Alpine and Kuparuk, sits Pikka. The Pikka unit is part of the Nanushuk Field which is estimated to hold as much as 1.5-billion barrels of oil. This is considered to be the biggest conventional onshore oil discovery in the US in the last 30-years. Upon full development, it is anticipated that Pikka will produce 120,000 barrels per day, and on some accounts up to 160,000 barrels per day. Conservatively, there is enough oil here to keep Pikka online for nearly 35-years.

Like Willow, there’s just no infrastructure in Pikka despite being sandwiched by two existing fields. Early planning on Pikka included budgetary Requests for Proposal which were submitted by Pikka’s Owner, Oil Search. One RFP requested multiple modules nearly 80’ H x 200’ L x 80’ W, a fairly typical example of the infrastructure which is required.

Finally, early testing has been going on in the Horseshoe unit of the North Slope (south of the Willow and Pikka unit) and early indication is that Horseshoe will also be a high volume area, with volume of over 1-billion barrels. Combined with Willow and Pikka, the makings of a modern day Prudhoe Bay is in the works and could be a generational project.

Aerospace

Vandenberg Air Force Base is home to the US Air Force, United Launch Alliance, Space X, and now home of the Space Force, a branch of the US Air Force. Blue Origin is looking at Vandenberg as well and this will produce new opportunities for launch facilities. The western range is advantageous and continues to serve the needs of the industry. All these groups are getting a boost from “REACH” (Regional Economic Action Coalition). Currently, Vandenberg has the only Space Launch Complex (SLC) to launch for polar orbit. The Cape is working on a program for this, but currently the capability does not exist.

 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 29 of 36

(Report from 'REACH' available for online viewing at <https://reachcentralcoast.org/wp-content/uploads/Phase-0-Report.pdf>)

Excerpt from the referenced report:

“Driven in large part by commercial enterprises, space is now a \$425-billion industry that’s expected to grow to \$3-trillion over the next three decades...It’s a huge opportunity and why REACH adopted building a thriving space enterprise as a core initiative in our 2030 plan.”

This bold plan by the State in collaboration with all the stake holders will result in the construction of new facilities to support launch efforts at Vandenberg. Launch towers and/or mobile assemble buildings will be major projects that will require work on very large structures within this decade. The work on these facilities in the past been done by NW Oregon/SW Washington fabricators – including Thompson Metal Fab. This work requires facilities with large yard areas and heavy fabrication capabilities as well as a barge loading facility that is capable of supporting ocean going barges. There are very few of these types of facilities on the West Coast. The Columbia Business Center is one of those few spaces and represents a location that has both barge loading capabilities and the manufacturing capacity through groups like Thompson Metal Fab.

Past work in California dating back to the 1960’s has been done at the Columbia Business Center. Jacket Liners for the Santa Barbara oil field were built at this location. Work for both Space Launch Complex 3 (SLC 3) and SLC 6 were done at Columbia Business Center. Much of this work required a full bridge raise to facilitate passage of the cargo on board a barge.

In addition to this planning at Vandenberg, Space X is now under contract for two more launches from there.

(https://www.noozhawk.com/article/defense_department_awards_contract_to_spacex_for_2_vandenberg_afb_launches)



Pictures from Space Launch Complex-6 on April 26, 2021 show before and during launch of United Launch Alliance Delta IV Heavy rocket carrying a classified spy satellite. The launch table was manufactured by Thompson Metal Fab and delivered to the jobsite in 2003.



 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 30 of 36

Excerpt from NOOZHAWK Santa Barbara:


“The Department of Defense awarded Space Exploration Technologies a pair of missions that will involve two rocket launches from Vandenberg Air Force Base for the military’s next-generation of space-based tools for warfighters....The announcement in the final hours of 2020 put the firm-fixed-price contract cost for SpaceX at \$150,450,000...The first launch will occur in September 2022, and the second mission will take place no later than March 31, 2023, to complete putting the constellation in space, according to the award by the Space Development Agency in Washington, D.C.”

SpaceX and United Launch Alliance have been awarded a 40%/60% split for launching DOD payloads. This award was made in August of 2020. For work at Vandenberg, SpaceX will have to add the capability of vertical integration of DOD payloads. This will require Space X to build a Mobile Service Tower (MST) or a similar structure to facilitate vertical integration of their vehicles. Currently SpaceX does all integration horizontally, installing satellites and rockets onto Falcon 9 and Falcon Heavy inside hangars near the company’s launch pads. But some of the of the US Government’s most sensitive and expensive intelligence-gathering satellites are designed to be mounted on their launch vehicles vertically. SpaceX officials have indicated that vertical integration capability is required of participants in the National Security Space Launch Phase 2 Launch Service Procurement.

Offshore Wind and Wave

Currently there are no independent organizations/companies willing to make the upfront investment into this emerging market. The land based wind industry grew because of federal tax credits that made it profitable, and without federal assistance it is unlikely that offshore systems will get the boost needed.

Recently, the administration under President Biden cited their plan to expand the use of off-shore wind farms in effort to develop renewable energy sources. The goal of the Biden Administration is to increase capacity of the current off-shore systems to power 10-Million homes by the year 2030. To meet that target, the administration intends to accelerate the permitting of projects along the coastlines and to open waters for development. \$3-Billion in federal loan guarantees are available for offshore wind projects and for investing in the nation’s port properties to support wind construction.



Mirroring this goal to develop offshore wind energy, the states of California and Oregon have introduced bills to develop wind energy along their coastlines. California bill AB525 sets a goal of 10GW of offshore wind by 2040,

 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 31 of 36

3GW of which to be established by 2030. Oregon’s HB3375 also sets a goal of 3GW by 2030. Oregon’s effort is sponsored by a Republican (Rep. David Brock Smith) who has positioned the states bill as an opportunity to stimulate economic development and resiliency.

Currently there is not a facility on the West Coast that is set up to assemble these massive offshore wind systems. Thompson Metal Fab certainly has the capacity to manufacture the floating bases, and the facility/space to receive the wind towers and turbines. We also have the space to perform all assembly required. All opportunity to participate with this emerging market is gone however if the new bridge is not at a suitable height. Our current plan to participate with this emerging market is to manufacture the bases at TMF and float them downstream to a satellite yard where the towers and turbines can be assembled and installed on our bases. With that plan in place, we can utilize our current facility for all the heavy manufacturing, and provided that we are not impacted by the height of the I-5 bridge, we can ship these structures to wherever the assembly yard is located. The Biden administration keys in on one important factor, most coastal port properties are not currently set up to handle this massive manufacturing and investment in the properties must be made.

Most of the current facilities manufacturing offshore structures are on the American East Coast, or in the Gulf. Even though these facilities have the capacity, they are not well positioned to support the manufacturing of offshore systems for the West Coast. To reach the West Cost, all cargo must travel through the Panama Canal and the distance associated with voyage makes the transportation very expensive and further defines the reason why developing a manufacturer on the West Coast is so important.



Figure A-20 Vancouver

Image above comes from BOEM report in 2016 which evaluates various sites on the West Coast that would be suitable for the development of offshore wind power manufacturing. The far right shows the Columbia Business Center, and predominantly in middle is Thompson Metal Fab.

Thompson Metal Fab is one of possibly two manufacturers on the West Coast who has the size of facility, yard space and direct access to water to make our company a very attractive option for full-scale manufacturing of offshore systems. When you look at the total capacity of the Columbia Business Park, there is more than enough space and infrastructure to use our location in a dynamic way. If the new bridge does not at least accommodate this emerging market, it will be very difficult to develop the required infrastructure at all on the West Coast. Let us not lose what we currently have.

 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 32 of 36

On March 3rd, 2016, the Bureau of Ocean Energy Management published a 256-page report that names the Columbia Business Park as a viable option for manufacturing offshore wind systems, but also notes that if the new height of the I-5 bridge is lowered below its current air gap it will severely restrict this type of manufacturing for any facility that is upstream of the bridge (i.e. Thompson Metal Fab).

To download a PDF file of the Environmental Studies Program report, go to the US Department of the Interior, Bureau of Ocean Energy Management, Environmental Studies Program Information System website and search for OCS Study BOEM 2016-011.



Images above comes from the 2016 BOEM report which shows the manufacturing and shipping capabilities of the Columbia Business Center for the wave power industry.

Burnside Bridge

The Burnside Bridge is scheduled for start of construction in 2024. There are two alternatives to the movable portion of the bridge: Replace the existing double-leaf bascule bridge with a vertical lift bridge – or – replace the bridge with a modern double-leaf bascule. The replacement of the approaches is difficult and would be best with a long span alternative. The option of a Tied-Arch, Cable-Stayed or Truss Span is attractive.



Image above shows the Sauvie Island Bridge being shipped to the jobsite via barge on the Willamette River and passing under the Burlington Northern RR Bridge in Portland, OR. Delivery of steel for the new Burnside Bridge would take a similar approach, due to the limited area for construction at the jobsite in downtown Portland, OR. Bridge steel coming from the Columbia Business Center would pass under the Interstate Bridge to reach the jobsite.

 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 33 of 36

Due to congestion at the job site, moving the major spans into place will be done by water. Similar work has been done in the past on the Freemont Bridge, Sauvie Island Bridge and Sellwood Bridge.

Golden Gate Bridge Seismic Retrofit

The Golden Gate Bridge has an upcoming project that is one of the largest projects on a single bridge that is not new construction. The iconic towers on the Golden Gate Bridge will be retrofitted in addition to the deck steel between the two towers. This project was due to be completed by 2024 but has been delayed by other projects (*currently scheduled to be complete in 2023*).

West Coast Movable Bridges

California has 36 movable (non-railroad) bridges. Of that group, four are in poor condition and 25 are in fair. Replacement will be recommended for some of these bridges and most will be shipped to the job-site by barge.

Oregon has the previously mentioned Burnside Bridge coming up. Additionally, the Rose Quarter Improvement project which will include the manufacturing of major steel spans.


Washington has 51 movable bridges (non-railroad). 10 are in poor condition and 34 are in fair condition. These bridges will be slow to replace due to budget issues but most of the poor condition bridges will be replace.

Hydroelectric Maintenance Projects

The current 2021 (fiscal year) budget work plan for the US Army Corps of Engineers is \$2.7-Billion. Much of this work will be on the Columbia River system. Applicable work for TMF is as follows:

Portland District

- Bonneville Dam
 - Powerhouse 2, 65-Ton Tailrace Gantry Crane Replacement
 - Headgate Repair Pit Rehab
 - Powerhouse 1 Trash Racks
 - Fish Guidance Efficiency
- John Day Dam
 - Navigation Lock Downstream Gate Bearing Shoe Replacement
 - Trash Racks Replacement
- Cougar Dam:
 - Spillway Gate Rehab
 - Butterfly Valves



 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 34 of 36

- Foster Dam:
 - Oil Spill Prevention
 - Oil Water Separator
 - Fish Weir Follow-on
- Detroit Dam:
 - Spillway Gate Rehab
- Dexter Dam:
 - Trash racks
 - Intake Gates
 - 25-Ton Intake Gantry Crane Replacement
- Green Peter Dam:
 - 180-Ton Bridge Crane Rehab
- Big Cliff Dam:
 - 40-Ton Intake Gantry Crane
 - Trash Racks and Gates Rehab

Seattle District

- Libby Dam
 - 75-Ton Intake Gantry Crane Rehab
- Albeni Falls Dam
 - Turbine Maintenance Platform
- Chief Joseph Dam
 - Intake Gates Rehab or Replacement
 - Turbine Maintenance Platform
 - 50-Ton Intake Gantry Crane Rehab
 - 18-Ton Tailrace Gantry Crane Rehab

Walla Walla District

- Ice Harbor Dam
 - Intake Gate Hydraulic System Upgrades
- Lower Monumental Dam
 - Turbine Maintenance Platform
- Lower Granite Dam
 - Turbine Maintenance Platforms

 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 35 of 36

Desalination in California

California is always in a water crisis. They have new reservoirs planned that will require outlet works, gates, etc. Most of this work will ship by truck/train, but shipping over the water (by barge) will be the modular structures for new equipment in the planned Desalination facilities that California needs to sustain the population growth.

30-miles north of San Diego is the Claude “Bud” Lewis Carlsbad Desalination Plant, the largest effort in North America to turn salt water into fresh water. Each day 100-million gallons of seawater are pushed through semi permeable membranes to create 50-million gallons of fresh water that is piped to municipal users. Carlsbad, which became fully operational in 2015, creates about 10% of the fresh water the 3.1-million people in the region use, at about twice the cost of the other main source of water. This is a real issue for California and will require the state to build more of these desalination plants.

Wartime Efforts

It is important to plan for the unforeseen as well. Contingency comes in many forms; but let us not lose sight of the reason why the facility exists to begin with. Kaiser built the facility as part of the war effort in WWII.

Because of the shipping clearances allowed when the drawbridge was at full height, the Vancouver Shipyards could produce Liberty and Victory war ships despite being upstream from the bridge. If that height is impacted by a fixed structure at a *lower* clearance, the ability for Thompson to support major wartime efforts is certainly

diminished especially when compared to the capacity we could offer today. As noted previously, we are one of only a handful of facilities on the West Coast who has facility large enough to manufacture the structures we do and ship over the water. Reducing shipping clearances will certainly limit Thompson’s ability to be a strategic West Coast manufacturer if a major wartime event occurs.



Henry Kaiser’s Vancouver Shipyard, shown in development in 1942. Eventually becoming the Columbia Business Center, this facility would become a strategic West Coast manufacturing facility.

IN CLOSING


Thompson Metal Fab supports the new Interstate Bridge Replacement project. The region has outgrown the capacity of the current span and a new bridge is needed to reflect current and future needs. Innovations in transportation have changed the way people travel and move goods since 1917; and modern engineering, materials, manufacturing, and construction should allow for a beautiful, robust structure that will serve the needs for future generations. Currently the lift span on the Interstate Bridge is 178’ at maximum clearance, any reduction

 THOMPSON METAL FAB	
Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Impact Statement	PG 36 of 36

on a new span will have significant impact on TMF's industrial competitiveness. Less clearance will inhibit Thompson's ability to attract job-producing industrial projects to the region. Lower bridge clearance will also cause constraints for current and future energy infrastructure needs where TMF is counted on to be a major supplier to energy producers. Impacts to clearance could also affect the development of renewable energy sources, such as offshore wind. A facility, like that at Thompson Metal Fab in the current configuration, will be critical in the success of offshore wind programs on the West Coast. Additionally, users such as the US Army Corps of Engineers, will be impacted as they depend on TMF to deliver structures by barge to support our region's dams and ports East of I-5.

We recognize a new Interstate Bridge replacement needs to meet the requirements of all modern and future modes of transportation, and that requirement will most likely impact our historical, current, and future usage of river transit. However, Thompson also recognizes the importance of a new, safe, and modern bridge to the region, and is willing to work with the Interstate Bridge Replacement project team to preserve Thompson Metal Fab and hundreds of family wage jobs, while at the same time advancing a much needed new bridge to the future.

Sincerely,




John B. Rudi
Owner/President
Thompson Metal Fab



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix A – Bridge Clearance Visual Aid	PG 1 of 1

Clearance information assumes Zero (0) Datum. The Columbia River is typically 3' to 7' higher than Zero Datum. That measurement is not reflected in the example below. River height may significantly reduce the lift span clearance when seasonal river flows are above zero datum levels.*



* <https://water.weather.gov/ahps2/hydrograph.php?wfo=pqr&gage=vapw1>




Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix B - River Usage Data	Page 1 of 1

EXAMPLES OF THOMPSON METAL FAB PROJECTS WHICH REQUIRED BRIDGE LIFT									
Owner	Project Name	Shipping Date	Shipping Destination	Number of Barges	Barge List, FT (height exposed above waterline)	Dunnage/Blocking Height (ft)	Height of tallest structure (ft)	USGC Minimum Gap (ft)	Total Required Clearance, FT (Assumes Zero Datum)
AKDOT	Ward Cove Ferry Dock Expansion	2020	Ketchikan, AK	1	25	5	14	10	54
Intel	LARK E-Houses	2020	Hillsboro, OR	1	25	5	16	10	56
ASE	Wind Tunnel Retrofit	2019	Tongue Point, OR	1	25	5	18	10	58
Hilcorp	Innovation Rig	July 2016	North Slope, AK	1	25	10	50	10	95
Multnomah County	Sellwood Bridge	2015-2016	Portland, OR	7	25	5	20	10	60
Furie	Monopod Pile	July 2014	Cook Inlet, AK	1	25	0	126	10	161
Saxon Drilling	Rig 147	July 2013	Kenai, AK	1	25	10	40	10	85
Saxon Drilling	Rig 169	July 2013	Kenai, AK	1	25	10	40	10	85
Parker Drilling	Rig 272	July 2011	North Slope, Alaska	1	25	10	113	10	158
Parker Drilling	Rig 273	July 2011	North Slope, Alaska	1	25	10	113	10	158
Doyon Drilling	Rig 25	July 2010	North Slope, Alaska	2	25	10	70	10	115
British Petroleum (BP)	Liberty Rig	July 2009	North Slope, Alaska	2	25	10	100	10	145
CalTrans	East Tie-In	2008-09	Bay Area, CA	2	25	5	40	10	80
OHSU	Portland Aerial Tram	2006	Portland, OR	1	25	10	33	10	78
CalTrans	Bay Bridge Retrofit	2006	Portland, OR	3	25	5	60	10	100
US Army Corps of Engineers	Ice Harbor RSW	March 2005	Portland, OR (Swan Island) and then to Ice Harbor Dam	1	25	5	68	10	108
Samuel Engineering	Alaska Gold Mining	2005	Nome, AK	1	25	5	50	10	90
CalTrans	Richmond San Rafael Retrofit	2004	Bay Area, CA	1	25	5	40	10	80
Boeing	Delta IV Launch Table	2003	Vandenberg AFB, CA	1	25	10	33	10	78
US Army Corps of Engineers	Lower Granite RSW	March 2001	Portland, OR (Swan Island) and then to Lower Granite Dam	1	25	5	61	10	101
Pool Arctic	Rig 9	1999	North Slope Alaska	1	25	10	60	10	105
Cascade General	Esperanza Power Barge	1999	Portland, OR	1	25	10	30	10	75
Pool Arctic	Rig 6	1998	North Slope, AK	1	25	10	60	10	105
PGE	Trojan Decommissioning	1998	Hanford, WA	1	25	5	40	10	80
Nordic-Calista	Rig 3	July 1997	North Slope, Alaska	1	25	10	78	10	123
LaFarge Cement	Pre-Heater Tower	1997	Richmond, BC, Canada	1	25	5	60	10	100
Cascade General	Golmar Explorer Ship Conversion	1997	Portland, OR	1	25	5	30	10	70
TriMet	Terry Moore Pedestrian Bridge	1996	Portland, OR	1	25	5	30	10	70
WSDOT	Duwamish Bascule Bridge	1996	Seattle, WA	1	25	5	30	10	70
CalTrans	Nimitz Freeway	1995	Bay Area, CA	4	25	5	70	10	110
Port of Sacramento	Bulk Material Handling System	1993	Sacramento, CA	1	25	5	50	10	90
Powell River Paper Company	Chlorine Dioxide Module	November 1991	British Columbia, Canada	1	25	5	76	10	116
Parker Drilling	Rig 245	July 1990	North Slope, Alaska	1	25	10	78	10	123
Pacific Marine	SWATH Hull	1989	Honolulu, HI	1	25	10	60	10	105
Christensen Marine	Dry Dock	1987	Vancouver, WA	1	25	10	40	10	85
ConocoPhillips	Milne Point Modules	1987	North Slope, AK	3	25	10	30	10	75
	Newport Bay Floating Foundation	1986	Portland, OR	1	25	5	20	10	60
WSDOT	I-90 East Channel Bridge	1986	Seattle, WA	1	25	5	30	10	70
ARCO	Housing Expansion	July 1985	North Slope, Alaska	1	25	5	65	10	105
Georgia Pacific	Wood Chip Material Handling System	1973	Toledo, OR	1	25	5	60	10	100

Bridge to be opened at Captain's discretion for loads under 72' high.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 1 of 27



This 1936 photo shows the waterfront property in Vancouver, WA where Henry Kaiser would develop the Vancouver Shipyard

Thompson Metal Fab is presently located near this area.



In just a few years nearly 200-acres was redeveloped, providing Vancouver a major industrial waterfront facility. An active Kaiser Shipyard is shown here in 1943



THOMPSON
METAL FAB

Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 2 of 27




In 1948, three years after WWII ended, the Vanport flood not only wiped out Oregon's second largest city, but it left the Kaiser Shipyards completely barren.



By 1956, the facilities at the current Columbia Business Center are in full operation once more, leveraging the capacity to support the industrial needs of the time.




Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 3 of 27



The development of offshore oil in California required the fabrication of massive infrastructure. Typically, offshore oil fabrication is done in the Gulf states, but with major oil production now on the West Coast those Gulf state areas could not lend support and a West Coast facility was required.

[1966]



Continued manufacturing of 'Jacket Liners' continues into the mid 1970's at the current day Columbia Business Center. In the lower right corner, two massive jacket liner side panels are visible.


Each of the Building 40 manufacturing bays are 80' W x 420' L, so using the facility as a scale, those side panels are nearly 120' W x 240' L

[1968]



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 4 of 27


A completed Jacket Liner segment being prepared for loadout. The slip shown here is not the one used currently by Thompson Metal Fab and the Columbia Business Center, but it served the same purpose – to load massive structures onto barges.



In this configuration, the jacket liner is estimated to be 120' tall, nearly double the size of the facility and similar in size to structures manufactured by Thompson Metal Fab still to this day


[1971]

Roofing being extended to Building 40, Bay 10-12 (current Thompson Metal Fab).



TMF Project Managers, early 1970's

Shortly after moving to Vancouver, TMF would enclose bay 5-9 with a roof and walls. A sign marked the location.






Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 5 of 27



Completed conveyor tubes, staged for barge loading in Thompson's yard.



At 300' long, this conveyor nearly takes up the entire length of a bay at TMF



A barge is being loaded with conveyors for delivery to Bay Area, CA




Conveyor systems and support towers were a major part of Thompson's first few decades at the Columbia Business Center. TMF's barge slip allowed for massive, modular deliveries to Ports, pulp & paper factories, and other industrial areas.




Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 6 of 27

*Completed conveyor project at the Port of Longview.
Thompson fabricated the conveyors and support towers.*



*Section view of modular conveyor segment,
nearly 40' W x 30' H*



There are numerous Ports on the Columbia River with large, developed properties and robust industrial activity. These Ports are critical to our region and are the hub for most incoming goods.

Conveyor systems are often used at Ports to quickly handle and transfer bulk materials. Thompson Metal Fab manufactured and delivered the massive conveyor system and support towers shown here and delivered to the Port of Longview.

Modular structures were loaded on a barge and erected in the field. Delivering modular units allows for quicker assembly in the field and easier integration of all mechanical components.

*Conveyor being loaded on barge at
Thompson Metal Fab.*





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 7 of 27




Conveyors come in many shapes and sizes, depending on the intended use. Shipping the structures pre-assembled saves on time and money in the long-run and is a value-add for Owners and other stakeholders. Shown here are additional examples of projects that were manufactured by Thompson and delivered all over the West Coast, from Toledo, OR to Sacramento, CA.






Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 8 of 27



Heavy ducting for baghouses requires a facility like Thompson's. They can accommodate the size of the infrastructure in their shop and ship over the water by barge. The large duct section shown here is nearly 30' high and over 100' long.



Structural tower inside Thompson's shop being outfitted with piping and ducting systems. This tower is well over 30' high.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 9 of 27

Field installed support tower and ducting fabricated by TMF.




Baghouse components being loaded on a barge from Thompson Metal Fab's facility

Nearly touching the rafters, this giant structural building will soon be outfitted with mechanical items prior to load out on the barge. The size of Thompson's facility provides value to project owners who seek out modular, turn-key solutions for their infrastructure needs.





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 10 of 27



Refineries on the West Coast are typically located on coastal properties or are otherwise accessible by deep water ports. In addition to capacity expansion and improvements, these facilities have processing vessels and other equipment that wear out over time and need to be replaced.

Shown here at the Phillips 66 facility in Rodeo, CA, Thompson Metal Fab fabricated a “prefractioner” tower which was 17’ diameter x 126’ L. Too large and heavy to ship over the road, this vessel was delivered by barge and direct to the jobsite.





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 11 of 27



By land, sea, and air! Completed tanks for Solvay Chemical (Longview, WA) were transported by barge from Thompson's facility. Tanks were then removed from the barge by helicopter and set in place at the jobsite.



Process vessels and skids are being loaded on a barge from Thompson Metal Fab's facility. This load will be delivered to Alaska and used on the North Slope. These units are well over 20' and 40' long.



Large tanks for Amalgamated Sugar in Portland, OR. The tanks are used as part of their manufacturing process. Due to the size of the tanks, they were shipped by barge and then transloaded to a truck for final delivery.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 12 of 27



Trunnions for the Interstate Bridge shown above in Thompson’s shop. Their proximity to the bridge made TMF an ideal location when repairs were needed. Shown below are two Seattle area bridge projects that were completed at the Columbia Business Center, painted by TMF, and delivered to the jobsite by barge.





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 13 of 27



These structures are 9' diameter x 132' long and part of a Small Waterplane Area Twin Hull (SWATH). Once assembled in Thompson's yard, the hull measured 53' wide and nearly 60' high once outfitted with the superstructure. Thompson's location adjacent to the Columbia River was a key part in earning this business. After testing in the river, the "Navatek" shipped to Hawaii where the vessel still operates.





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 14 of 27



Barge load approaching the Interstate Bridge after leaving Thompson Metal Fab. TMF's massive facility is seen in the background.



Shown above and below is a modular segment of the Power Barge fabricated by TMF. Segments were pre-fabricated in the shop before being assembled in Thompson's yard. The final assembly was 105' W x 30' H x 284' L






Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 15 of 27



At left, large platform is being flipped inside Thompson Metal Fab's shop.




Thompson Metal Fab has a legacy of fabricating unique, complex, and often massive structures which require delivery by water.



Onlookers watch as the floating platform for the Newport Bay restaurant in downtown Portland, OR is launched. The platform was fabricated by Thompson Metal Fab.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 16 of 27




Pictures of platforms being manufactured for the Alaskan North Slope oilfields during the mid-1980's. The size of these structures cannot be understated, the workers standing on top provide scale.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 17 of 27


Shown below, load out of the cradle base that would carry PGE's Trojan nuclear reactor. TMF fabricated the base and the shielding enclosures.



Support towers nearing the Interstate Bridge. This load is headed for the Port of Sacramento upon completion at Thompson Metal Fab



Barge full of skid modules approaching the Interstate Bridge after fabrication by TMF.




The lower segment of the iconic Portland Aerial Tram's tower is shown inside Thompson Metal Fab's shop. Including the bunking underneath, the tower is nearly 40' high and 30' wide. The completed tower can be seen at OHSU, spanning over I-405.






Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 18 of 27



Fabrication of the Lower Monumental Dam Lift Gate is shown at left inside Thompson's shop. Due to its size (nearly 1.5-Million pounds) the gate was fabricated in three segments, loaded on a barge, and finished in the field by the General Contractor. The picture here shows the three segments be aligned for fit verification at TMF's yard. Final dimensions are 88' W x 84' H



Rivaling the size of the original gates at the Panama Canal, these Miter Gates for The Dalles Dam are 55' W x 110' L. Each gate (two total) weighed 1-Million pounds. For scale purposes, the 'flash' on the left side near the gate is a welder performing work. There is also a person standing near the ladder at the front. Both gates were loaded on a barge for direct delivery to the jobsite.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 19 of 27



Many of the structures fabricated by TMF require the use of specialty moving systems for handling around the shop and for loading barges. Shown here, an SPMT (Self Propelled Modular Transporter) is used to move one of the Ward Cove Reaction Dolphins from TMF's Bay 8 and out to the barge slip for loading. Each reaction dolphin is 30' x 30' x 12' H



Barge load out for the Ward Cove Ferry Terminal Expansion project. All structures were fabricated at the Columbia Business Center, including the Transfer Span and Reaction Dolphins which were completed by Thompson. The Transfer Span, shown near the back of the barge is 14' H x 140' L. These structures were delivered direct to the jobsite in Ketchikan, AK.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 20 of 27



The scale of Thompson’s facility and access to a barge slip has made TMF a strategic partner for many river users, including the US Army Corp of Engineers who count on TMF’s capability to produce the large infrastructure needed for the Columbia & Snake River dams. Shown here, a prototype ‘surface collector’ for Bonneville Dam in the early 1990’s.





Shown above and below are multiple barge loadings for a massive project at Lower Granite Dam in the mid-1990’s. All structures were fabricated by Thompson Metal Fab and loaded out at the Columbia Business Center.





Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 21 of 27

Load out of housing modules manufactured by Thompson Metal Fab. This housing will be used for the workers on Alaska’s North Slope.



Enclosed modules to be used for a drilling rig, shown inside TMF’s shop

Modular fabrication has long been a part of Thompson’s history and success. The size of their facility at the Columbia Business Center allows TMF to offer large, turn-key, fully-operational modular systems which get used for housing, data centers, oil production/drilling, crude oil processing, technology, electrification, water treatment, chemical processing, fuel storage, pipe handling, and conveyor systems – among other uses. Remote jobsite locations and size of many of these structure require use of the barge slip, adjacent to Thompson’s facility.



Example of processing modules being manufactured inside Thompson Metal Fab



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 22 of 27



Walls, roof, and equipment being installed on 44' x 97' skid shown below

Thompson's extensive experience with turn-key modular systems made it a valuable partner as a new market emerged for these products. Increase demand for technology pushed groups, like Intel, to expand their facilities. 'Cloud based' data storage requires facilities on the ground that can house servers. Increased online shopping (i.e. Amazon) requires warehouses and data centers. As the world becomes dependent on technology the demand for these custom, modular buildings has significantly increased.



Shown below in late 2019, this skid represents the largest non-oil related module manufactured by TMF. At 44' W x 97' L, this module is too large to ship over the road, and too big to be handled in the field.

To accommodate field conditions, a shipping 'split' was engineered in the middle of the floor (shown) and in the roof trusses. The 44-ft mega module would ship via barge, and completely outfitted in two segments.



Two 44' x 97' modules were manufactured by TMF, each with a shipping split described above. Shown in the middle of this picture are two of the four total segments prior to barge loading.


Also shown is the BNSF Wind River Bridge. This was manufactured at the Columbia Business Center and would ship via barge completely assembled and installed in one-piece.




Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 23 of 27




Pool Arctic Rig 3 Retrofit, performed by TMF



In the late 1990's, Thompson Metal Fab would retrofit Pool Arctic's Rig 6 with a new, modern moving system. A TMF foreman provides scale to the size of the wheels used on the rig.



Manufacturing Pool Arctic's Rig 9 inside TMF.



At 60' W x 30' H, this is one of many modules manufactured for Pool Arctic Rig 9




Following some of its recent predecessors (i.e. Rig 245), Rig 9 would use the 'mega module' concept to reduce downtime on the North Slope



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 24 of 27

Over the last 30-years, 15 rig projects have been awarded to Thompson Metal Fab. Nearly 1/3rd of the rigs in Alaska have some connection to TMF.

Shown at right, Nordic-Calista's Rig 3 being 'rigged up' in Thompson's yard in 1997. This workover rig is used to restore production on exiting wells.




Parker Drilling Rig 245 passes under the Interstate Bridge after being manufactured by Thompson Metal Fab. The first of its kind on the North Slope of Alaska, Rig 245 is made of fewer 'mega modules' instead of multiple smaller modules. This mitigates risk, reduces downtime, and is highly attractive for the drilling contractor. Thompson Metal Fab is the only facility capable of providing this service on the West Coast.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 25 of 27



No, the picture to the right is not the inside of a 'big box' store, but it is the size of one! This is the inside of the Liberty Rig's Pipe Module (see above) and is where all production drill pipe is stored.



At the time it was manufactured, the Liberty Rig was the world's largest land-based drilling rig. Everything about this rig was supersized, including the mast shown here inside Thompson Metal Fab. Drill structures, like the one shown here, require special certification for manufacturing, and TMF is the only facility on the West Coast who holds that certification while also boasting a facility/yard of its size, in addition to roll-on/roll-off barge capabilities.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 26 of 27




For new rig builds, drilling contractors traditionally manage the design and hire their own sub-contractors (structural, electrical, mechanical, etc.) For Doyon Drilling's Rig 25, TMF was hired as the General Contractor and managed all rig-build efforts on behalf of Doyon. As a result, Rig 25 becomes the rig built by Thompson as General Contractor. Rig 25 is a sought after work-horse on Alaska's North Slope and is a dependable rig in Doyon's fleet. This picture shows a very proud Thompson team at the end of the project.



Thompson Metal Fab	Revision 0
Interstate Bridge Replacement Project	May 26, 2021
Appendix C – Photo Gallery	PG 27 of 27



Shown above is the part of the substructure base for Rig 272. Its twin (Rig 273) was manufactured at the same time at TMF. Picture below shows the yard assembly of Rig 272, Rig 273, and Rig 25.



Nearly touching the rafters inside Thompson Metal Fab, the 'Innovation Rig' stands looming in the shadows. This rig was built for Hilcorp in 2016.



The Interstate Bridge looks on in the distance as Thompson Metal Fab manufactures three rig projects from their Columbia Business Center facility. Shipping clearance on Rig 272 & 273 (blue) would be nearly 160'.

Marine Industries and Fabricators

Company: Vigor

Company provided the following information to the IBR Program.

Vigor Works, LLC. is a Heavy Industrial Fabrication Company that serves the Marine, Hydro-Electric, Nuclear, Oil & Gas and Steel Bridge Industries. The wide variety of products produced by Vigor Works support private industry as well as Government Agencies (local, state, federal). Past and present projects completed from the Columbia Industrial Park include fully assembled final products: Bridges, Oil Field Modules/Platforms, Marine Vessels and other extremely large infrastructure type goods which have limited areas for fabrication due to water loadout/shipping and air draft restrictions.

Vigor Works (in and adjacent to the Columbia Industrial Park) are uniquely qualified and situated to support strategic and industrial needs, particularly our national infrastructure of dams, locks and bridges and marine vessels. The living wage trade jobs created by this work are critical to the health of the Vancouver/Portland area. Vigor currently supports ~1500 trade related jobs in the Portland Metro area which includes three separate locations in and around the Columbia Industrial Park.

Heavy investment in capital and people has occurred in all three Vancouver locations upriver of the I-5 bridge. By maintaining flexibility to pursue and provide ultra large product for customers, we can continue to pursue this type of work to support the jobs and economy of Vancouver. Our sites are unique due to their access to a large metro area with truck, rail and marine access.

The current bridge height has been important for commerce and shipments along the Columbia River for nearly a century and even more critically important since the war effort in the 1940s. In the late sixties and early seventies, offshore drilling rigs were constructed at this location and had to transit under the bridge. These offshore platforms required the bridge to be raised to its full height of 174 feet to allow them to pass under the raised span. More recently we have watched drilling equipment destined for Alaska being assembled in the Columbia Industrial Park that required 150 feet of clearance to be shipped down the river. Vigor consistently evaluates opportunities for product up to 110 feet in height. The additional height of blocking, transport barge freeboard and clearance margin, easily results in an air draft requirement of 130' for these projects. Ideally, we recommend a height of 150 feet air draft.

Our other Portland facility located on Swan Island (Portland Shipyard) also engages in large fabrications and we have in the past, barged components to/from the Vancouver facilities. Our Marine Fabrication work has also resulted in portions of vessels being shipped via barge to Ketchikan and we are currently evaluating shipping product components to our Seattle Shipyard- the exact size of those products have not yet been determined. In the future, we would expect to ship product both upriver and down river.

The lower height of the bridge will limit Vigor Works' ability to compete on some projects. The ability and direct access to shipping on the Pacific Ocean and subsequent trade routes to Alaska or the gulf coast and Mississippi River system (via the Panama Canal) is critical for our full and sustained operation. One recent project was delivered to New Jersey.

In summary:

The Bridge Height is now is 174 feet; this height has been needed as follows:

- 1960 to 1975 Drilling Platforms for the California Offshore Field.
- 1980 to 1995 Various loads from the Industrial Park to locations in Alaska and elsewhere.

- 2000 to 2012 Drilling Equipment for Parker Drilling assembled in the Park and shipped to Alaska.

Current:

- We are evaluating Vancouver for long term production related to partial or all construction for upcoming work. The final bridge height could impact the amount of work completed in Vancouver.
- We anticipate there will be some opportunity for future module or drill platform work associated with Alaska as equipment requires replacement.
- We expect, although do not know what the development of offshore wind will need for industrial shore side support.

Conclusion:

This Marine Highway is used by a multitude of users with traffic going both upstream and down. We ship goods from the industrial park upstream of the bridge to Swan Island Ship Yard and from the Swan Island Ship Yard to the industrial park. The I-205 Bridge upstream of the bridge has a clearance of 144 feet and downstream of the bridge we have clearance limited only at Astoria and that is 196 feet with the Lewis and Clark (Longview) bridge over 200 feet. We believe it is critical to our business and the viability of the river system used for commerce to keep the height of this bridge at least 150 feet.